



November 25, 2025

To: City of Marco Island Water and Sewer
807 E Elkcarn Circle
Marco Island, FL 34145

Attn: Eric Dial, Jeff Poteet

Re: Marco Island Source Water Facility Pump Station Surge Relief Valve Replacement Proposal

Quote#:101625 CP1 rev3

Please see the equipment proposal listed below which shall be per City of Marco Island's Standard terms and conditions of sale. If proposal is accepted by the City it would cancel out the repair PO's #00250300 for \$44,214.29 for repair of the same valve

Equipment Included:

(1) 18" Ross Valve Model 42WR-S Pump control valve with:

- Class 250# Flanges, ASTM A-126 Class B Cast Iron Body & Cover
- Electric check and emergency quick close features
- Bronze Internals (ASTM Specification B-584)
- Globe Full-Ported Piston Style Construction with 20" internals
- Internal/External coating of NSF 61 Coating on all Ferrous Surfaces.
- Approximate Shipping Weight: 3500 lbs. Freight Included
- Startup, testing and O&M training included

Your Total Cost for Valve Equipment Listed above, with no sales tax included is:


\$52,000.00

EES Terms and Conditions

1. We do not include sales tax, pressure gauges, anchor bolts, conduit, tools, toolboxes, lubricants, installation, spare parts, control panels or any other items which are not specifically called out in this scope of supply.
2. Under no circumstances will EES, LLC or its suppliers be liable for any incidental, consequential, liquidated or late delivery damages whatsoever.
3. Payment terms are 90% net 30 days from delivery of equipment onsite listed herein, and 10% retainage released after factory startup has been performed or within 60 days of startup,

- whichever comes first. Any unpaid balance 30 days past due being subject to interest at 1-1/2% per month being added to the unpaid balance, with approved credit.
4. Pricing is based upon EES, LLC's Conditions of Sale. No other terms or conditions of sale will apply unless accepted in writing by an authorized member of the Company.
 5. The following lead times are estimates only based on market conditions at the time of the proposal and are conditional on acts of force majeure outside of the company's control.
 - Submittal Data Available: Included
 - Estimated Shipment of Equipment: 22-24 weeks from customer's written approval to release equipment to production.

We provide submittals for the customer's approval to ensure that we have the correct perception of what is required for the project. This proposal was developed based on the direct valve replacement for serial numbers L88355. Approval of the submittal confirms that you have reviewed the information included herein and on any attachments. It shall also confirm that the equipment, services, and configuration offered herein and included in the submittal is correct. Any order you provide us for equipment will be contingent upon your approval of provided submittals which, when approved, shall become the only specifications for the equipment manufactured for your project.



Cory Peavy - President
Environmental Equipment Services, LLC
C (863) 640-0201