

City of Marco Island, Collier County, FL

**Tigertail Lagoon/ Sand Dollar Island Ecosystem Restoration Project  
Operational Maintenance 2026**

\*\*\*Quote Schedule\*\*\*

**Contract No.: 21-7885 Collier County**

Item	Description	Unit of Measure	Multiplier	Unit Price	Total
1	Mobilization & Demobilization	Lump Sum	1		11,500
2	Excavation of shoaled area within the sand trap up to 7,000 cubic yards, transporting sand for disposal along the Sand Dollar Island permitted template (travel range 1.5 mile), placement on the beach berm grading to template.	Lump sum	1	105,000	105,000
3	Additional volume dredged excavated from shoaled area within the sand trap	Cubic yards	2,000	15	30,000
4	Grading and tiling the constructed berm between R-129 and R-133	Lump sum	1	9,500	9,500
				<b>Total</b>	156,000

Notes:

Please refer to the attached Construction Plans and the following notes:

- 1) Mobilization and Demobilization of mechanical excavation equipment including at minimum one large or long reach excavator, one off road truck and one dozer plus supporting equipment.
- 2) The project schedule aims to avoid bird and sea turtle nesting season, as such the work is intended to occur between January 2, 2026, and February 15, 2026
- 3) Surveying and environmental monitoring requirements are not included in this quote and will be provided by third parties under continued services with the City of Marco Island.
- 4) Quantities listed are estimated based on available monitoring data to date.

Company Name:

EarthTech Enterprises inc  
239-571-0204

Authorized Signature:

