City of Marco Island VETERANS' COMMUNITY PARK FINAL AND APPROVED 60%
CONSTRUCTION DOCUMENT
ESTIMATE July 31, 2020 Manhattan Build ng excellend Prepared by: Prepared for: **David Puls** Timothy E. Pinter, P.E. **Project Director** Public Works Director Manhattan Construction City of Marco Island 3705-1 Westview Drive 50 Bald Eagle Drive Naples, Florida 34104 Marco Island, Florida 34145 (239) 643-6000 dpuls@manhattanconstruction.com





City of Marco Island

Final & Approved 60%
Construction
Document Estimate

Prepared for:

Timothy E. Pinter, P.E. Public Works Director City of Marco Island 50 Bald Eagle Drive Marco Island, Florida 34145

Prepared by:

Manhattan Construction 3705-1 Westview Drive Naples, Florida 34104

Contact Person at Manhattan:

David Puls, Project Director dpuls@manhattanconstruction.com (239) 643-6000

Contents

Executive Summary

- 1. Itemized Schedule of Values
 - General Summary
 - ICE Detailed Estimate
- 2. Project Schedule
- 3. Value Engineering Log
- 4. Assumptions, Clarifications & Allowance Log
- 5. Site Management Plan
- 6. Document Log



July 31, 2020

Mr. Timothy E. Pinter, P.E. Public Works Director 50 Bald Eagle Drive Marco Island, FL 34145

RE: City of Marco Island Veterans' Community Park

Dear Mr. Pinter:

Manhattan Construction is pleased to provide you with the 60% Construction Document Budget for the City of Marco Island Veterans' Community Park (MIVP). This deliverable is based upon the 60% Construction Document plans dated April 3, 2020 from Kimley-Horn as well the Restroom and Band Stand Building 50% Design Development Documents dated April 3, 2020.

Included with this Deliverable are various supporting documents as follows:

- General Summary Estimate
- MC2 ICE Detailed Estimate
- Project Schedule
- Assumptions, Clarifications & Allowance Log
- Value Management Log and Detail
- Site Management and Phasing Plan
- Document Log

General Summary

Work Item	Total Cost
Park Construction:	\$7,147,666
Restroom Building:	\$471,334
Band Stand Building:	\$1,905,183

Total 60% Construction Document Budget:	\$9,524,182
Accepted Value Engineering:	(\$689,851)
Project Budget Including Value Engineering:	\$8,834,331



BUDGET DEVELOPMENT

Manhattan has produced a detailed estimate for the scope of work included in the 60% Construction Documents dated April 3, 2020 valued at \$9,524,182. This budget is based on a full estimate of all quantities and unit prices applied from historical data, input from local subcontractors on the larger work items and a review of the estimate with the design team on July 13, 2020. This budget includes a 7% design contingency to allow for further development of the design and this budget assumes an 11-month construction schedule.

ALLOWANCES

With ever early estimate for a projects, certain elements of the work are not sufficiently defined to either completely quantify or to acquire cost opinions from vendors and therefore allowances are used as reasonable placeholder values in the budget. For the MIVP project, only five items required the use of an allowance which are listed on page 8 of the clarifications and amount to less than 5% of the value of the project. These work items will be further defined in the next design package and most allowances will be converted to firm prices.

CONTINGENCIES

This budget includes a 7% design contingency and a 3% construction managers GMP contingency. When the next phase of the design documents are priced, the design contingency will be reduced and eventually eliminated at GMP if all design items are fully defined.

VALUE ENGINEERING

Manhattan and the design professionals, in conjunction with review by City of Marco Island, conducted several value engineering work sessions to prepare options that would reduce the project budget. The value engineering options accepted by the City of Marco Island in the amount of \$689,851 has established the current project budget at \$8,834,331. Although not all value engineering option were acceptable, the team established the budget and scope and the next design stage to produce the 90% construction documents in underway. The schedule for production of the next design stage documents was established for September 1, 2020.

SCHEDULE

A preliminary schedule has been develop by the construction team that will build the project. The budget aligns with the 11-month schedule for construction and 1-month for closeout. However, there is a need for the ability to expedite long lead items prior to the final GMP which includes underground structures, light fixtures, louvers, trellis work, playground, permeable pavers, structural steel and playground equipment. Expediting these materials from the 90% construction documents will be needed in an attempt to counter the effect of the current unpredictable deliver of long lead materials. Just before these packages are awarded, the 100% construction documents will be issued to the low bidders to confirm that the price aligns with the final design.



SITE MANAGEMENT AND PHASING

The site management plan has been established for the construction period and it was decided by the project team that the project site would be completely closed so that the construction would proceed unencumbered by any phasing and therefore allowing the fastest completion of the entire project.

NEXT STEPS

All value engineering options have been presented, vetted and those that have been accepted will be incorporated into the design. It was decided that one add bid alternate will be priced at bid time to install permeable pavers in lieu of sod in a portion of the park for overflow parking. The 90% construction documents are underway and will be produced by September 1, 2020. Manhattan will begin the development of the bid package requirements when the 90% construction documents are completed.

GMP DEVELOPMENT

The development of the GMP begins by preparing comprehensive bid packages to be issued with the next set of documents. The bid packages will describe in great detail the scopes of work for the final bid process and assist with the solicitation process for the early packages needed for the long lead materials identified above.





SECTION 1

ITEMIZED SCHEDULE OF VALUES

- GENERAL SUMMARY
- ICE DETAILED ESTIMATE



Estimate Dated: June 30, 2020

Project Name: MARCO ISLAND VETERAN'S COMMUNITY PARK

Manhattan
Building excellence.

11 MONTHS DURATION

6,475 TOTAL GROSS SQFT (RESTROOM & BAND STAND)

ed Date: July 30, 2020

	60% CONSTRUCTION	N DOCUMEN TTAN CONS		E SUMMARY				
Bld Pkg No.	Scops of Work	01 PARK	10 RESTROOM BLDG	20 BAND STAND	TOTAL	Cost / Acre	Cost / Bldg SQFT	% of Total
BP01A	GENERAL CONDITIONS: STAFF	715,125			\$ 715,125	100,439	0	7.51%
BP01B	SAFETY	7,490	-	-	\$ 7,490	1,052	0	
BP01C	TEMPORARY ELECTRIC CONSUMPTION - TRAILER	5,500			\$ 5,500	772	0	
BP01D	TEMPORARY WATER CONSUMPTION - TRAILER	1,100			\$ 1,100	154	0	0.01%
BP0D.1	TEMPORARY WATER CONSUMPTION - JOBSITE	1,100			\$ 1,100	154	D	
BP01E	TEMPORARY TOILETS - HOLDING TANK	3,850			\$ 3,850	541	0	0.04%
BP01F	TEMPORARY TELEPHONE - TRAILER	1,760	*		\$ 1,760	247	0	0.02%
BP01G	JOBSITE TRAILER	41,390		_	\$ 41,390	5,813	0	0.43%
BP01I	POSTAGE	6,050		-	\$ 6,050	850	0	0.08%
BP01J	PLAN REPRODUCTION	1,200			\$ 1,200	169	0	0.01%
BP01K	JOB SIGANGE - TEMP WAYFINDING	1,500		-	\$ 1,500	211	0	0.02%
BP01L	PROGRESS PHOTOS	1,650	-	_	\$ 1,650	232	0	0.02%
BP01M	SMALL TOOLS / EQUIPMENT	8,350	-		\$ 8,350	1,173	0	0.09%
BP01N	TEMPORARY LABOR	11,000			\$ 11,000	1,545	0	0.12%
BP010	DUMPSTERS	27,000			\$ 27,000	3,792	0	0.28%
BP01Q	FINAL CLEANING	10,000	-	-	\$ 10,000	1,404	0	0.10%
BP02A	SURVEYS	60,000		:,	\$ 60,000	8,427	0	0.83%
BP02D	SELECTIVE SITE DEMOLITION	121,006			\$ 121,006	16,995	0	1.27%
BP03A	CONCRETE	95,720	23,195	108,528	\$ 227,443	13,444	20	2.39%
BP04A	CMU MASONRY / PRECAST COPINGS / STONE VENEER	188,204	59,408	89,212	\$ 336,824	26,433	23	3.54%
BP05A	STRUCTURAL STEEL - METAL JOIST - METAL DECK	100,204	00,400	656,978	\$ 656,978	20,433	101	6.90%
BP05C	MISCELLANEOUS METALS			38,150	\$ 36,150	0	6	0.38%
BP06A	ROUGH CARPENTRY: WOOD TRUSSES / ROOF SHEATHING		11,980	30,130	\$ 11,980		2	0.38%
BP06C	FINISH CARPENTRY - WOOD TRIM	35,280	13,950		\$ 49,230	4,955	2	0.13%
BP06D	MILLWORK	55,260	3,445		\$ 3,445	4,855	4	
BP07A	WATERPROOFING / JOINT SEALANTS		3,550	3,800	\$ 7,350	0		0.04%
BP07A BP07C	METAL ROOF PANELS		60,966	162,697	\$ 223,663	0	35	
BP07D	WALL SIDING PANELS: ALUMINUM FASCIA & SOFFIT PANELS		9,276	102,007	\$ 9,276			2.35%
			9,270	15 420		0	1	0.10%
BP07E	MEMBRANE ROOFING HM DOORS / HM FRAMES / WOOD DOORS / HARDWARE &			15,426	\$ 15,426	0	2	0.16%
BP08A	INSTALLATION		6,400	9,600	\$ 16,000	0	2	0.17%
BP08B	ENTRANCES / STOREFRONTS / GLASS & GLAZING		950	2,600	\$ 3,550	0	1	0.04%
BP08C	SPECIAL DOORS: OVERHEAD COILING DOORS	-	10,000		\$ 10,000	0	2	0.10%
BP09A	STUCCO		45,325	85,232	\$ 130,557	0	20	1.37%
BP09B	DRYWALL & METAL FRAMING		12,270	5,543	\$ 17,813	0	3	0.19%
BP09C	ACOUSTICAL / ACOUSTICAL CEILINGS		-	31,680	\$ 31,680	0	5	0.33%
вроэн	PAINTING & COATINGS	432	7,910	71,317	\$ 79,659	61	12	0.84%
DD404	DIVISION 10 MISC. SPECIALTIES (TLT PARTN / ACCESSORIES / FIRE		00.050	7.400	44.050			
BP10A	EXT)	7 000	33,850	7,400	\$ 41,250	0	8	0.43%
BP10D	FLAGPOLES	7,000	4.500	0.500	\$ 7,000	983	0	0.07%
BP10E	SIGNAGE / IDENTIFYING DEVICES	25,000	1,500	3,500	\$ 30,000	3,511	1	0.31%
BP10G	LOUVERS / VENTS		225	89,465	\$ 89,690	0	14	0.94%
BP10I	FIRE EXTINGUISHERS / CABINETS	***	800	800	\$ 1,600	0	0	0.02%
BP10L	ALUMINUM TRELLIS	368,250	-	45.000	\$ 368,250	51,721	0	3.87%
BP11E	PROJECTION SCREENS	400.077	-	15,000	\$ 15,000		2	0.16%
BP12E	SITE FURNISHINGS	469,673	0.000	00.000	\$ 469,673	65,965	0	4.93%
BP21A	FIRE SUPPRESSION SYSTEM		2,288	22,000	\$ 24,286	0	4	0.25%
BP22A	PLUMBING	- 0	64,014	24,575	\$ 88,589	0	14	0.93%
BP23A	HVAC (HEATING, VENTING & AIR-CONDITIONING)	100.000	16,000	19,250	\$ 35,250	0	5	0.37%
BP26A	ELECTRICAL	190,000	6,604	35,750	\$ 232,354	26,685	7	2.44%
BP31A	EARTHWORK	260,179		05.700	\$ 260,179	36,542	0	2.73%
BP31F	SPECIAL FOUNDATIONS: CONCRETE PILES	900 745	-	95,700	\$ 95,700	07,430	15	1.00%
BP32A BP32B	ASPHALT PAVEMENT / CURBS CONCRETE PAVING / STAMPED CONCRETE	693,715	-		\$ 693,715 \$ 267,066	97,432	0	7.28%
BP32B BP32C	UNIT PAVING - BRICK PAVERS	267,068 402,563			\$ 267,066 \$ 402,563	37,509 56,540	0	2.80% 4.23%
BP32E	SYNTHETIC FIELD TURF / SURFACES	298,778			\$ 298,778	41,963	0	3.14%
BP32F	TEMPORARY CHAIN LINK FENCE & GATES	36,700			\$ 36,700	5,154	0	0.39%
BP32H	PLANTING / SOD / TREES	480,472			\$ 480,472	67,482	0	5.04%
BP32i	IRRIGATION	126,563			\$ 126,563	17,776	0	
BP32M	BOARDWALKS	563,615			\$ 563,615	79,159	0	1.33%
BP32M BP33A	SITE UTILITIES: WATER / SANITARY / STORM SEWER	526,235			\$ 526,235	79,159	0	5.92%
J. 50/1	The state of the s	520,200			020,200	10,008	- 1	U.353 /6
	Subtotal	6,060,516	393,904	1,592,203	8,046,622	1,130,144	307	84.49%

Estimate Dated: June 30, 2020

Project Name: MARCO ISLAND VETERAN'S COMMUNITY PARK

Monhotton Building excellence. ised Date: July 30, 2020

11 MONTHS DURATION

6,476 TOTAL GROSS SQFT (RESTROOM & BAND STAND)

	60% CONSTRUC	TION DOCUMEN	IT ESTIMATE	SUMMARY				
	MAN	NHATTAN CONS	TRUCTION					
Bld Pkg No.	Scope of Work	01 PARK	10 RESTROOM BLDG	20 BAND STAND	TOTAL	Cost / Acre	Cost / Bldg 8QFT	% of To
	Cross Check Subtotal	6,060,516	393,904	1,592,203	8,046,622			
6.000%	Sales Tax (Included in Items Above)				Inci Above			7
1.500%	Subcontractor Default Insurance	78,247	5,909	23,883	108,038			
	Subtotal Cost of Work	6,138,763	399,812	1,616,086	8.154,661			85.62
0.000%	Owner's Contingency (By Owner)		-	28				
7.000%	Design Contingency	365,152	27,573	111,454	504,179	-		
3.000%	MCF Construction Contingency	156,494	11,817	47,768	216,077		Later Control	
	Subtotal Cost of Work	6,660,408	439,203	1,775,306	8,874,916			93,18
-	Builder's Risk (By Owner)		-		(4)			
0.242%	IT, Scheduling & PROCORE	16,118	1,063	4,296	21,477			
	Building Permit & Plan Review Fees (By Owner)		*	+				
	Subtotal	6,676,526	440,266	1,779,602	8,896,394			93.41
1.175%	Construction Manager Insurances	78,449	5,173	20,910	104,533	20,1		
	Subtotal	6,754,975	445,439	1,800,513	9,000,926			94.51
0.732%	CM Payment & Performance Bond	52,326	3,450	13,947	\$69,723	94117		
5.000%	MCF Profit & Fee	340,365	22,444	90,723	453,532			
TAL PROJE	CT COST	7,147,666	471,334	1,985,183	9,524,162			100.00
TAL ACCEP	PTED VALUE MANAGEMENT AMOUNT AS OF JULY 30, 2020				(689,851)			
/ISED TOTA	AL WITH ACCEPTED VALUE MANAGEMENT				8,834,331			

Marco Island Veterans Park

Manhattan Construction Company 3705 Westview Drive, Suite 1 Naples, FL 34104

Phone:239643-6000 Fax: 239595-8737

Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK, MARCO ISLAND, FL

Estimator: JFB Primary Project Qty: 0 SF Estimate UM:Imperial

Sort Sequences: 1. Area
2. Bid Packages
3. Not Used

4. Not Used

Report DOES NOT include Taxes & Insurance or Indirect Costs.

		Labor	Material	Equipt	Sub	Temp	Equipt	Other	Total	Item
Description	Quantity	\$	\$	\$	\$	Mati \$	Rntl \$	Costs \$	Unit \$	Total \$
BP01A GENERAL CONDITIONS	STAFF									
	12.00 MONTH				21,372.00				21,372.00	256,4
	12.00 MONTH				21,961.00				21,961.00	263,5
	12.00 MONTH				9,822.00				9,822.00	117,8
	1.10 MONTH				16,712.00				16,712.00	18,3
	3,67 MONTH				10,649.00				10,649.00	39,0
	2.00 MONTH				9,916.00				9,916.00	19,8
	ONS: STAFF				\$715,125					\$715,1
BP01B SAFETY										
AID KITS & REFILLS	11.00 MONTH				40.00				40.00	4
EQUIPMENT & SUPPLIES	11.00 MONTH				550.00				550.00	6,0
TOUS CONTROL	1.00 LSUM				1,000.00				1,000.00	1,0
kages BP01B SAFETY					\$7,490				·	\$7,4
BP01C TEMPORARY ELECTRIC	CONSUMPTION -									
	11.00 MONTH				500.00				500,00	5,5
	TRIC				\$5,500					\$5,5
BP01D TEMPORARY WATER CO	ONSUMPTION -									
RARY WATER SERVCE /	11.00 MONTH				100.00				100.00	1,1
	BP01A GENERAL CONDITIONS: CT MANAGER (11-MONTHS + TH CLOSEOUT) INTENDENT (11-MONTHS + TH CLOSEOUT) CT ENGINEER (11-MONTHS + TH CLOSEOUT) CT ENGINEER (11-MONTHS + TH CLOSEOUT) R SAFETY MANAGER (1/10 TIME ONTH) OFFICE MANAGER (1/3 TIME ONTH RACT ADMINISTRATOR ITHS @ 1/3 TIME) RACT ADMINISTRATOR ITHS @ 1/4 TIME ITHS @ 1/4 T	BP01A GENERAL CONDITIONS: STAFF CCT MANAGER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) RINTENDENT (11-MONTHS + 12.00 MONTH TH CLOSEOUT) CCT ENGINEER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) R SAFETY MANAGER (1/10 TIME 1.10 MONTH ONTH) OFFICE MANAGER (1/3 TIME 3.67 MONTH ONTH) CACT ADMINISTRATOR 2.00 MONTH HAS 2.00 MONTH WAS 2.00 MONTH W	BP01A GENERAL CONDITIONS: STAFF CCT MANAGER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) INTENDENT (11-MONTHS + 12.00 MONTH TH CLOSEOUT) CCT ENGINEER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) R SAFETY MANAGER (1/10 TIME 1.10 MONTH ONTH) OFFICE MANAGER (1/3 TIME 3.67 MONTH ONTH) OFFICE MANAGER (1/3 TIME 3.67 MONTH ONTH CACT ADMINISTRATOR 2.00 MONTH WAS 1/3 TIME) REACT ADMINISTRATOR 2.00 MONTH WAS 1/3 TIME) REQUIPMENT & SUPPLIES 11.00 MONTH EQUIPMENT & SUPPLIES 11.00 MONTH TOUS CONTROL 1.00 LSUM REQUIPMENT & SUPPLIES 11.00 MONTH TOUS CONTROL 1.00 LSUM REQUIPMENT & TRAILER 11.00 MONTH TOUS CONTROL 1.00 LSUM REACT POWER / TRAILER 11.00 MONTH TOUS CONTROL 1.00 LSUM REQUIPMENT & SUPPLIES 11.00 MONTH TOUS CONTROL 1.00 LSUM REQUIPMENT & SUPPLIES 11.00 MONTH TOUS CONTROL 1.00 LSUM REACT POWER / TRAILER 11.00 MONTH TOUS CONTROL 1.00 MONTH TO	BP01A GENERAL CONDITIONS: STAFF CCT MANAGER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) RINTENDENT (11-MONTHS + 12.00 MONTH TH CLOSEOUT) CCT ENGINEER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) R SAFETY MANAGER (1/10 TIME 1.10 MONTH ONTH) OFFICE MANAGER (1/3 TIME 3.67 MONTH ONTH ACCT ADMINISTRATOR 2.00 MONTH ITHS @ 1/3 TIME) RAGGES BP01A GENERAL CONDITIONS: STAFF BP01B SAFETY AID KITS & REFILLS 11.00 MONTH EQUIPMENT & SUPPLIES 11.00 MONTH FOUS CONTROL 1.00 LSUM RAGGES BP01B SAFETY BP01C TEMPORARY ELECTRIC CONSUMPTION - DRARY POWER / TRAILER 11.00 MONTH IMPTION RAGGES BP01C TEMPORARY ELECTRIC ON - TRAILERS BP01D TEMPORARY WATER CONSUMPTION -	BBP01A GENERAL CONDITIONS: STAFF CCT MANAGER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) RINTENDENT (11-MONTHS + 12.00 MONTH TH CLOSEOUT) CCT ENGINEER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) R SAFETY MANAGER (1/10 TIME 1.10 MONTH ONTH ONTH ONTH ONTH ONTH ONTH ONTH	### BP01A GENERAL CONDITIONS: STAFF ICT MANAGER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) INITENDENT (11-MONTHS + 12.00 MONTH 21,961.00 TH CLOSEOUT) ICT ENGINEER (11-MONTHS + 12.00 MONTH 9,822.00 TH CLOSEOUT) ICT ENGINEER (11-MONTHS + 12.00 MONTH 10,712.00 MONTH 10,712.	BP01A GENERAL CONDITIONS: STAFF 12.00 MONTH 121,372.00 121,372	BP01A GENERAL CONDITIONS: STAFF	BP01A GENERAL CONDITIONS: STAFF	BP01A GENERAL CONDITIONS: STAFF CT MANAGER (11-MONTHS + 12.00 MONTH TH CLOSEOUT) 11-MONTHS + 12.00 MONTH TH CLOSEOUT) 21,961.00 21,961.00 21,961.00 11-MONTHS + 12.00 MONTH TH CLOSEOUT) 9,822.00 9,822.00 9,822.00 9,822.00 16,712.00 10,649.00 1

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

					RAN'S COM		Aiut			7/9/202
Item Code Description	Quantity	Labor	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total Unit \$	Item Total \$
Total Bid Packages BP01D TEMPORARY WATER					\$1,100					\$1,10
Bid Packages BP01D.1 TEMPORARY WATE	ER CONSUMPTION -									
540,005 ICE & CUPS Total Bid Packages BP01D.1 TEMPORARY V - JOBSITE	11.00 MONTH WATER CONSUMPTION				100.00 \$1,100				100.00	1,10 \$1,10
Bid Packages BP01E TEMPORARY TOILET	S - HOLDING TANKS									
510.296 TEMPORARY TOILETS (3-TOTAL)	11.00 MO/EA				255,00				255,00	2,8
510.310 TRAILER HOLDING TANK	11,00 MONTH				95,00				95.00	1.0
Total Bid Packages BP01E TEMPORARY TO TANKS	DILETS - HOLDING				\$3,850					\$3,8
Bid Packages BP01F TEMPORARY TELEPH	HONE - TRAILERS									
510,215 TEMPORARY TELEPHONE (TRAILER SERVICE)	11.00 MONTH				160.00				160,00	1,7
			1 1							
Total Bid Packages BP01F TEMPORARY TE	LEPHONE - TRAILERS				\$1,760				ŀ	\$1,7
Total Bid Packaģes BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS										\$1,7
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX)	11.00 MONTH				1,200.00				1,200.00	
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK	11.00 MONTH 11.00 MONTH				1,200.00 270.00				1,200.00 270.00	13,2
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 620.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS	11.00 MONTH 11.00 MONTH 11.00 MONTH				1,200.00 270.00 65.00					\$1,7 13,2 2,9 7
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK	11.00 MONTH 11.00 MONTH				1,200.00 270.00				270.00	13,2 2,9 7
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 620.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS	11.00 MONTH 11.00 MONTH 11.00 MONTH				1,200.00 270.00 65.00				270.00 65.00	13,2 2,9 7
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS	11.00 MONTH 11.00 MONTH 11.00 MONTH 1.00 SETS				1,200.00 270.00 65.00 480.00				270.00 65.00 480.00	13,2 2,9
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 620.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 620.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION	11.00 MONTH 11.00 MONTH 11.00 MONTH 1.00 SETS 1.00 SETS				1,200.00 270.00 65.00 480.00 480.00				270.00 65.00 480.00 480.00	13,2 2,9 7 4
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION 520.200 RAMP - KNOCKDOWN & RETURN	11.00 MONTH 11.00 MONTH 11.00 MONTH 1.00 SETS 1.00 SETS				1,200.00 270.00 65.00 480.00 480.00 875.00				270.00 65.00 480.00 480.00 875.00	13,2 2,9 7 4 4
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION 520.200 RAMP - KNOCKDOWN & RETURN 520.210 ADA / IBC STEP DELIVERY & SETUP	11.00 MONTH 11.00 MONTH 11.00 MONTH 1.00 SETS 1.00 SETS 1.00 EACH 1.00 EACH				1,200.00 270.00 65.00 480.00 480.00 875.00				270.00 65.00 480.00 480.00 875.00	13,2 2,9 7 4 4 8 8
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION 520.200 RAMP - KNOCKDOWN & RETURN 520.210 ADA / IBC STEP DELIVERY & SETUP 520.220 ADA / IBC STEP DISMANTLE & RETURN	11.00 MONTH 11.00 MONTH 11.00 MONTH 1.00 SETS 1.00 SETS 1.00 EACH 1.00 EACH 1.00 EACH				1,200.00 270.00 65.00 480.00 480.00 875.00 875.00 187.50				270.00 65.00 480.00 480.00 875.00 875.00 187.50	13,2 2,8 7 4 4 8 8 8
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION 520.200 RAMP - KNOCKDOWN & RETURN 520.210 ADA / IBC STEP DELIVERY & SETUP 520.220 ADA / IBC STEP DISMANTLE & RETURN 520.230 BLOCK & LEVEL	11.00 MONTH 11.00 MONTH 11.00 MONTH 11.00 SETS 1.00 SETS 1.00 EACH 1.00 EACH 1.00 EACH				1,200.00 270.00 65.00 480.00 480.00 875.00 875.00 187.50				270.00 65.00 480.00 480.00 875.00 875.00 187.50	13,2 2,9 7 4 4 8 8
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION 520.200 RAMP - KNOCKDOWN & RETURN 520.210 ADA / IBC STEP DELIVERY & SETUP 520.220 ADA / IBC STEP DISMANTLE & RETURN 520.230 BLOCK & LEVEL 520.240 DELIVERY & FREIGHT	11.00 MONTH 11.00 MONTH 11.00 MONTH 11.00 SETS 1.00 SETS 1.00 EACH 1.00 EACH 1.00 EACH 1.00 EACH				1,200.00 270.00 65.00 480.00 480.00 875.00 875.00 187.50 940.00				270.00 65.00 480.00 480.00 875.00 875.00 187.50 187.50	13,2 2,8 7 4 4 8 8 8 1 1
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION 520.200 RAMP - KNOCKDOWN & RETURN 520.210 ADA / IBC STEP DELIVERY & SETUP 520.220 ADA / IBC STEP DISMANTLE & RETURN 520.230 BLOCK & LEVEL 520.240 DELIVERY & FREIGHT 520.250 TEARDOWN	11.00 MONTH 11.00 MONTH 11.00 MONTH 11.00 SETS 1.00 SETS 1.00 EACH 1.00 EACH 1.00 EACH 1.00 EACH 1.00 EACH				1,200.00 270.00 65.00 480.00 480.00 875.00 875.00 187.50 187.50 940.00 430.00				270.00 65.00 480.00 480.00 875.00 875.00 187.50 187.50 940.00 430.00	13,2 2,8 4 4 8 8 8 1 1 1
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 520.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 520.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION 520.200 RAMP - KNOCKDOWN & RETURN 520.210 ADA / IBC STEP DELIVERY & SETUP 520.220 ADA / IBC STEP DISMANTLE & RETURN 520.230 BLOCK & LEVEL 520.240 DELIVERY & FREIGHT 520.250 TEARDOWN 520.260 RETURN FREIGHT	11.00 MONTH 11.00 MONTH 11.00 MONTH 11.00 SETS 1.00 SETS 1.00 EACH 1.00 EACH 1.00 EACH 1.00 EACH 1.00 EACH 1.00 EACH				1,200.00 270.00 65.00 480.00 480.00 875.00 875.00 187.50 187.50 940.00 430.00 2,500.00				270.00 65.00 480.00 480.00 875.00 875.00 187.50 187.50 940.00 430.00 2,500.00	13,22 2,9 7 4 4 8 8 8 1 1 1
Total Bid Packages BP01F TEMPORARY TE Bid Packages BP01G JOBSITE TRAILERS 520.140 60x24 REDIPLEX (56x24 BOX) 620.150 ADA / IBC RAMP W/ SWITCHBACK 520.160 ADA / IBC STAIRS 520.170 STATE APPROVED BUILDING PLANS 620.180 STATE APPROVED RAMP / STAIRS PLANS 520.190 RAMP - DELIVERY & INSTALLATION 620.200 RAMP - KNOCKDOWN & RETURN 520.210 ADA / IBC STEP DELIVERY & SETUP 620.220 ADA / IBC STEP DISMANTLE &	11.00 MONTH 11.00 MONTH 11.00 MONTH 11.00 SETS 1.00 SETS 1.00 EACH 1.00 EACH 1.00 EACH 1.00 EACH 1.00 EACH 2.00 EACH 1.00 EACH				1,200.00 270.00 65.00 480.00 480.00 875.00 187.50 187.50 940.00 430.00 2,500.00 430.00				270.00 65.00 480.00 480.00 875.00 875.00 187.50 187.50 940.00 430.00 2,500.00	13,2 2,8 4 4 4 8 8 1 1 1 9 8 8 2,6

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

40. 44DM	Entimenta I	CIA, MADOO ISI AAD	VETEDNIC	ADK 2020 0	ant VETE				EAUS OLINSU	rance or Indire	
46:44PM	Estimate	File: MARCO ISLAND							0.1		7/9/20:
Item Code	Description	Quantity	Labor \$	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rnt! \$	Other Costs \$	Total Unit \$	Item Total \$
Bid Packag	es BP01G JOBSITE TRAILERS										
1523,175 OFFI	CE SUPPLIES	11.00 MONTH				680.00				680.00	7.4
1 524,150 TOO	L & STORAGE SHEDS	6.00 MONTH				125,00				125.00	7
Total Bid Pa	ckages BP01G JOBSITE TRAILERS					\$41,390					\$41,3
Bid Package	es BP01I POSTAGE										
1525.150 POS	TAGE / FEDEX / UPS	11.00 MONTH		1 1		550.00				550.00	6.0
Total Bid Pa	ckages BP01I POSTAGE					\$6,050					\$6,0
Bid Packag	es BP01J PLAN REPRODUCTION										
330.105 ADDI	ITIONAL DRAWINGS	1.00 LSUM		1 1		1,200.00				1,200,00	1,2
Total Bid Pa	ckages BP01J PLAN REPRODUCTION	NC				\$1,200				1,2	\$1,2
Bid Packag	es BP01K JOB SIGNAGE - TEMP W	AYFINDING									
1580.200 TEM	PORARY SIGNS / SIGNS	1.00 LSUM				1,500.00				1,500.00	1,5
Total Bid Pa	ickages BP01KJOB SIGNAGE - TEN	IP WAYFINDING				\$1,500				,,,,,,,,,,,	\$1,5
Bid Package	es BP01L PROGRESS PHOTOS										
	GRESS PHOTOS	11.00 MONTH		1 1		150.00				150.00	1,6
Total Bid Pa	ckages BP01L PROGRESS PHOTOS	5				\$1,650					\$1,6
Bid Package	es BP01M SMALL TOOLS / EQUIPM										
1701.010 SUR	VEY EQUIPMENT	1.00 LSUM		1 1		1,200.00				1,200.00	1,2
720.100 SMAI	LL TOOLS	11.00 MONTH		1 1		550.00				550.00	6,0
	, GREASE & OIL	11.00 MONTH		1 1		100.00				100.00	1,1
Total Bid Pa	ickages BP01M SMALL TOOLS / EQ	UIPMENT				\$8,350					\$8,3
Bid Package	es BP01N TEMPORARY LABOR										
740.145 CLEA MON	AN UP PERIODICAL (1-WEEK PER	11.00 WEEK				1,000.00				1,000.00	11,0
	ckages BP01N TEMPORARY LABOR	₹				\$11,000					\$11,0
Bid Package	es BP010 DUMPSTERS										
740.125 DUM	PSTERS	90.00 PULLS				300.00				300.00	27,0
Total Bid Pa	ckages BP010 DUMPSTERS					\$27,000					\$27,0
Bid Package	es BP01Q FINAL CLEANING										
1740.170 FINA 1-FIN	L CLEAN UP (1-PRELIMINARY & IAL)	2.00 EACH				4,500.00				4,500.00	9,0
	L CLEAN GLASS CLEAN	1.00 LSUM				1,000,00				1,000.00	1,0
Total Bid Pa	ckages BP01Q FINAL CLEANING					\$10,000					\$10,0

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

Report DOES NOT include Taxes & Insurance or Indirect Costs.

	ILE FILE. MIANCO ISLAM	D VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK								7/9/202	
tem Description	Quantity	Labor \$	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rnti \$	Other Costs \$	Total Unit \$	Item Total \$	
Bid Packages BP02A SURVEYS											
701.005 LICENSED SURVEY	1.00 LSUM				60,000.00				60,000,00	60,0	
Total Bid Packages BP02A SURVEYS					\$60,000					\$60,0	
Bid Packages BP02D SELECTIVE SITE DEM	IOLITION										
400.010 DEMO, PALMS	26.00 EACH				75.00				75.00	1,9	
400.015 DEMO, TREES	28.00 EACH				75,00				75.00	2,1	
400.020 RELOCATE DESIGNATED TREES (BY LANDSCAPE)	9.00 EACH										
400.025 DEMO, ASPHALT PAVEMENT	9,046.00 SQYD				3,50				3.50	31,0	
400,030 DEMO, BUILDING	456.00 SQFT				18.00				18.00	8,	
400,035 DEMO, CONCRETE SLABS / SIDEWALKS	9,342.00 SQFT				3,55				3,55	33,	
400.040 DEMO, CURBS & GUTTERS	3,182.00 LNFT		1		4.25				4.25	13,	
400.045 DEMO, DRAINAGE, MES & END SECTIONS	1.00 EACH				75.00				75.00		
400.050 DEMO, DRAINAGE, PIPE (SIZE UNKNOWN)	89.00 LNFT				75.00				75.00	6,	
400.055 DEMO, DRAINAGE, STRUCTURES	10.00 EACH				750.00	1			750.00	7,	
100.065 DEMO, FENCE	439.00 LNFT				3,00				3.00	1,	
100.070 DEMO, GRAVEL	224.00 SQYD				5.00				5.00	1,	
100.075 DEMO, LIGHT POLE	1.00 EACH				750.00			1	750.00		
100.080 DEMO, PAVERS	1,449.00 SQFT				6.25				6.25	9	
100.085 DEMO, SIGN	36.00 EACH				35.00				35.00	1,	
100.090 DEMO, WOOD DECK	441.00 SQFT				6.00				6.00	2,	
Total Bid Packages BP02D SELECTIVE SITE	DEMOLITION				\$121,006					\$121,	
Bid Packages BP03A CONCRETE (FORM / R FINISH / CRANES)	REBAR / PLACE &										
310.012 CONCRETE: WALL FOOTING @ EXTERIOR WALL SIGN (37-LNFT @ 4.75'Wx1.25'D)	8.14 CUYD				355.00				355.00	2,	
#15.005 CONCRETE: WL-101~SEAT WALL FOOTING (4-SQFT PER LNFT) (11/H-06) (BASED ON 170 LNFT)	24.89 CUYD				425.00				425,00	10,	
315.025 CONCRETE: WL-101~SEAT WALL (6-SQFT PER LNFT) (11-H-06) (BASED ON 170 LNFT)	37.78 CUYD				1,350.00				1,350.00	51,	
317,005 CONCRETE: TRELLIS 1, 2, 3 & 4 COLUMN FOOTINGS 5.5' X 5.5' X 1.167'	52.30 CUYD				355.00				355.00	18,	

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

Report DOES NOT include Taxes & Insurance or Indirect Costs.
COMMUNITY PARK 7/8

2:46:44PM	
Item	
Code	

Estimate File: MARCO ISLA	ND VETERNS PARK 2020.0.est	- VETERAN'S COMMUNITY PARK

Item Code	Description	Quantity	Labor \$	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total Unit \$	Item Total \$
Bid Packages B	PO3A CONCRETE (FORM / RE	BAR / PLACE &									
FINISH / CRANE	ES) TE: TRELLIS 1, 2, 3 & 4	9.06 CUYD				1,400,00				4 400 00	40.00
	AL 1,75' X 1.75' X 2.0'	9,00 C010				1,400.00				1,400.00	12,68
Total Bid Packa FINISH / CRANE	ges BP03A CONCRETE (FORM :S)	/ REBAR / PLACE &				\$95,720					\$95,72
Bid Packages B	PO4A CMU MASONRY & PRE-	CAST COPINGS									
4220,317 CMU: EXT	TERIOR SIGNAGE WALL	166.00 SQFT				22.00				22.00	3,65
4220.319 CMU: EXT @ WALL	TERIOR SIGNAGE COLUMNS	84.00 SQFT				28.00				28.00	2,35
4225.500 CMU: POI BEAM (51	URED CONCRETE BOND LNFT)	1,00 CUYD				385.00				385.00	38
4227.500 CMU: REF TRELLISE	F: H-08~16" SQ COLUMNS @ ES	718,20 SQFT				28.00				28.00	20,110
	F: 4/H-08 16" SQ X 16" TK TE CAP @ 16" SQ COLUMNS	3.47 EACH				2,585.00				2,585.00	8,970
1420.005 COQUINA SIGN WA	A STONE~BLOCK VENEER @ LL	250.00 SQFT				48.00				48.00	12,00
VENEER	1&2 CONQUINA BLOCK COLUMNS (1/H-08)	1,632.00 SQFT				48.00				48,00	78,33
COLUMN		544.00 SQFT				48,00				48,00	26,11
COLUMN		544.00 SQFT				48,00				48.00	26,11
@ SIGN V		2.00 EACH				185,00				185.00	37
1730.015 3" TK. GR SIGN V @	ANITE WALL CAP 1.0' DEEP VALL	37.00 LNFT				65.00				65.00	2,40
(REF: 4/H	ANITE WALL CAP 18" SQ -08) COLUMNS	40.00 EACH				185.00				185.00	7,40
Total Bid Packa	ges BP04A CMU MASONRY & I	PRE-CAST COPINGS				\$188,204					\$188,20
Bid Packages B	POSC FINISH CARPENTRY - W	OOD TRIM									
SEAT CAI	EAT WALL: 2"X3" WOOD P~DETAIL 11/H-06 (6-RUNS	1,008.00 LNFT				35.00				35.00	35,280
	N IPE) (168 LNFT) ges BP06C FINISH CARPENT R	Y - WOOD TRIM				\$35,280					\$35,28
Bid Packages B	P09I PAINTING & COATINGS										
	CKSIDE OF GATEWAY SIGN	192.00 SQFT				2.25				2.25	433
Total Bid Packag	ges BP09I PAINTING & COATIN	IGS				\$432					\$43

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

2:46:44PM

Report <u>DOES NOT</u> in clude Taxes & Insurance or Indirect Costs. Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK 7/9/

Item			Labor	Material	Emilet	Out	Torre	Constant	Other		
Code	Description	Quantity	Labor	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total Unit \$	Item Total \$
Bid Packages BP1										C.i.i.	1014
0700.000 SITE FLAGP	DLE	1.00 EACH				7,000.00				7,000.00	7,00
Total Bid Packages	BP10DFLAGPOLES					\$7,000				","	\$7.00
Bid Packages BP1	DE SIGNAGE / IDENTIFYING	DEVICES				''					
0140.000 SIGNAGE AL		1.00 ALLW				25,000,00				25,000.00	25,00
Total Bid Packages	BP10E SIGNAGE / IDENTIF	YING DEVICES				\$25,000				20,000.00	\$25,00
Bid Packages BP1	OL ALUMINUM TRELLIS					,,					
0715.050 (SF-105) ALU		2.00 EACH				101,250.00				101,250.00	202,50
0715.060 (SF-105) ALU		1.00 EACH				60,750.00				60,750.00	60,75
	3'X70' (REF: 2/H-08)	1.00 EACH				105,000.00				105,000.00	105,00
	BP10L ALUMINUM TRELLIS	5				\$368,250					\$368,25
Bid Packages BP1	2E SITE FURNISHINGS										
PIECE; ŤWIS	ST SCULPTURAL PLAY T.15-90.297.015, (1/H-11)	1.00 EACH				130,000.00				130,000.00	130,00
	JLPTURA SCULPTURAL SCULPTUR.03 (2/H-11)	1.00 EACH				32,500.00				32,500.00	32,5
(BREAKDOW	NT CHESS GAME SYSTEM 'N FOLLOWS)	1.00 LSUM				20,000.00				20,000.00	20,00
TECTURA EX (2/H-07) **PR	NT CHESS GAME; 18 X18 (PRESSIONS PAVERS ICE IN GIANT CHESS EM, COMPLETE	28.00 SQYD									
	ONCRETE BASE (2/H-07) IANT CHESS GAME	5.00 CUYD									
	NT CHESS GAME; 1 ND (2/H-07) **PRICE IN S GAME SYSTEM,	1.00 CUYD									
GRANITE MI) (2/H-07) **PR	NT CHESS GAME; KAFKA ((ASSUMED 6 WIDE) ICE IN GIANT CHESS EM, COMPLETE	1.00 CUYD									
2670.020 (PG-105) ICO PING PONG (2,00 EACH				12,000.00				12,000.00	24,00

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

2:46:44PM

Report DOES NOT include Taxes & insurance or indirect Costs, Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK 7/9

Maria				14-4-4					5 4		71972020
Item Code	Description	Quantity	Labor	Material	Equipt	Sub \$	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total Unit \$	Item Total \$
	BP12E SITE FURNISHINGS	Quantity	_				Miles V	- Falls	00313 \$	Unit	IOEM \$
	1) APRIL ROUND TABLE BY	17.00 EACH				1,800.00				1,800,00	30,600
	RE (7/H-12)	Tr.oo EAOT				1,000.00				1,600.00	30,000
	2) APRIL CHESS TABLE BY IE (6/H-12)	6.00 EACH				1,100.00				1,100.00	6,600
12670.035 (SF-103 (5/H-12	3) APRIL CHAIR BY VESTRE	53.00 EACH				800.00				800.00	42,400
12670.040 (SF-104	4) RELOCATED BENCH (10/H-06)	29,00 EACH				500.00				500.00	14,500
	7) CUDDLY BENCH BY MALIK DOR (1/H-12)	9.00 EACH				4,500.00				4,500.00	40,500
	8) BLOC SUN BENCH BY EE (9/H-12)	6.00 EACH				3,400.00				3,400.00	20,400
	9) SMALL FORUM BICYCLE BY VESTRE (3/H-12)	5.00 EACH				650,00				650.00	3,250
	D) LARGE FORUM BICYCLE BY VESTRE (4/H-12)	3.00 EACH				800.00				800.00	2,400
	1) BLOCK LITTER BIN BY SE (10/H-12)	5,00 EACH				2,750.00				2,750.00	13,750
12670.070 (SF-113	3) ÙRBAN BOLLARDS BY E (11/H-12)	11.00 EACH				450.00				450.00	4,950
	4) MOVE BENCH BY VESTRE	4,00 EACH				2,900.00				2,900.00	11,600
12670.080 (SF-115	5) UTILITY BOLLARDS (12/H-12)	19,00 EACH		1 1		2,500.00				2,500.00	47,500
	B) AIR LOUNGE HAMMOCK BY (4/H-11)	3.00 EACH				4,500.00				4,500.00	13,500
	6) ARBOR TRELLIS SWING KDOWN FOLLOWS)	2.00 EACH								i	
	5) CONCRETE SLAB ON GRADE: CK 10.042' X 12.5'	251.05 SQFT				7.00				7.00	1,757
12670.202 (SF-116 HEIGH	6) WOOD POST 6X6 <=12.0' T	8.00 EACH				125.00				125.00	1,000
12670,203 (SF-116 LENGT	6) 2X8 GRAB BARS <=14.0'	16.00 EACH				55.00				55.00	880
12670,204 (SF-116	6) 2X8 SLOPED RAFTERS <=16.0'	8.00 EACH				65.00				65.00	520
12670,205 (SF-116	6) 2X4 PURLINS <=16.0	14,00 EACH				30.00				30.00	420
12670.206 (SF-116	S) ALUMINUM ROOF 14.5'X14.5'	420.50 SQFT				12.00				12,00	5,046
,	5) TRELLIS SWING	2.00 EACH				800.00				800.00	1,600
	kages BP12E SITE FURNISHINGS					\$469,673					\$469,673
Bid Packages	BP26A ELECTRICAL										
		1.00 ALLW				125,000,00				125,000,00	125,000
											65,000
	BP26A ELECTRICAL GHTING	1,00 ALLW 1,00 ALLW		7		\$469,673 125,000.00 65,000.00				125,000.00 65,000.00	

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

2:46:44PM

Report DOES NOT include Taxes & Insurance or Indirect Costs. Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK 7/9

2:46:44PM	Estimate	File: MARCO ISLAND	VE IEKNS P	AKK 2020.0	.est - VEIE	RAN'S COM	INIUNITY	PARK			7/9/2020
Item Code	Description	Quantity	Labor	Material S	Equipt \$	Sub	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total Unit \$	item Total \$
	kages BP26A ELECTRICAL	- Country			_	\$190,000			00000	Olar 4	\$190,000
						\$130,000					\$130,000
	BP31A EARTHWORK										
	T SWEEP / CEAN STREETS	5.00 MONTH				450.00				450,00	2,250
31200,000 TEMPO CONST	DRARY GRAVEL FRUCTION ENTRANCE (5/C-02)	2.00 EACH				3,250.00				3,250.00	6,500
31200.002 MOBIL	IZATION	1.00 LSUM				60,000.00				60,000.00	60,000
31200.005 CLEAR	ING & GRUBBING, LIGHT	7.12 ACRES				3,400.00				3,400.00	24,208
31200.010 EXCAV	ATION	9,455.00 CUYD				6,00				6.00	56,730
31200,015 EMBAN	KMENT	4,334.00 CUYD				6.00				6.00	26,004
31200,020 FINISH	GRADING	18,333,00 SQYD				2.75				2,75	50,416
	n) EARTHWORKS, IMPORT FILL, CK OF BENCH TO ROCK NG	283,00 CUYD				18.00				18.00	5,094
	1) 3" PERFORATED PIPE W/	170.00 LNFT				14.00				14.00	2,380
(ASSUI	n) DRAINAGE STONE, #57 MED) (1'-3" WIDE X 3'-6" DEEP X LONG = 744 CF = 28 CY	28.00 CUYD				22.00				22.00	616
31250.000 BARRI 1/C-02	CADES, TREES: SEE DETAIL	1,829.00 LNFT				6,00				6.00	10,974
31250.005 FLOAT	ING TURBIDITY BARRIER	467,00 LNFT				13.00				13.00	6,071
31250,010 INLET	PROTECTION SYSTEMS	13.00 EACH				250.00				250,00	3,250
AT PRO	ENCE (ASSUMED PLACEMENT DJECT LIMITS AROUND SITE; N SITE PLANS)	3,249.00 LNFT				1.75				1.75	5,686
Total Bid Pack	kages BP31A EARTHWORK					\$260,179					\$260,179
Bid Packages MARKINGS	BP32A ASPHALT PAVING - CUI	RBS - GUTTERS -									
	G EXISTING ASPHALT MED 2-1/2)	3,250.00 SQYD				11.00				11.00	35,750
CONCE	PE FC 9.5 ASPHALTIC RETE (INCLUDING MILLED & SPHALT AREAS) (PER SECTION -09)	14,175.00 SQYD				7.50				7.60	106,313
CONCE	TYPE SP 12.5 ASPHALTIC RETE (INCLUDING MILLED & SPHALT AREAS) (PER SECTION -09)	14,175.00 SQYD				13.50				13.50	191,363
32100.020 8" LIMI	EROCK BASE W/ PRIME, 00 (PER SECTION A-A / C-09)	14,175.00 SQYD				13.00				13.00	184,275

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

Report DOES NOT include Taxes & Insurance or Indirect Costs.

	44	

2:46:44PM	Estimate	FIIe: MARCO ISLANI	D VETERNS P	ARK 2020.0	.est - VETE	RAN'S COM	IMUNITY I	PARK			7/9/2020
Item Code	Barrier		Labor	Material S	Equipt	Sub	Temp Mati \$	Equipt Rntl \$	Other	Total	Item
	Description	Quantity	\$,	\$	wau >	raiti \$	Costs \$	Unit \$	Total \$
	P32A ASPHALT PAVING - CUF	RBS - GUTTERS -									
MARKINGS	RADE STABILIZATION.	14.175.00 SQYD				4.00				4.00	56,700
	ER SECTION A-A / C-09)	14,175,00 6Q1D				4.00				4,00	50,700
32100.030 PRIME & T SURFACE		3,250.00 SQYD				1.00				1.00	3,250
VALLEY G	ALLEY GUTTER (INCLUDED BUTTER AS SHOWN IN A-A / C-09)	1,550.00 LNFT				20.00				20.00	31,000
32100,050 6"X12" HE	ADER CURB	856,00 LNFT				12.00				12.00	10,272
32100,055 TYPE D C	URB	3,112,00 LNFT				16.00			1	16,00	49,792
32100.060 WHEELST	OPS, CONCRETE	140,00 EACH				75.00				75.00	10,500
32100.065 12 WHITE CROSSING	E STRIPE, PEDESTRIAN G	184.00 LNFT				3.00				3.00	552
32100,070 24 WHITE	E STOPBAR	58,00 LNFT				5,00			1	5.00	290
32100.075 6 BLUE S	TRIPE, PARKING STRIPE	248.00 LNFT		1		1.25	1			1,25	310
32100.080 6 WHITE	STRIPE, PARKING STRIPE	4,699.00 LNFT				1.25				1.25	5,874
	PPED PARKING SIGN, MOUNTED	8.00 EACH				750,00				750.00	6,000
32100.090 HANDICAF PAINT	PPED PARKING SYMBOL,	8.00 EACH				75.00				75.00	600
32100,095 STOP SIG	N (R1-1)	5.00 EACH				175.00				175.00	875
Total Bid Packag - MARKINGS	es BP32A ASPHALT PAVING -	CURBS - GUTTERS				\$693,715					\$693,715
Bid Packages BI CONCRETE	P32B CONCRETE PAVING & S	TAMPED					0				
3000.000 (H-101) CC	ONCRETE SIDEWALK, 4 00 PSI, 6 X6 W10 WWF	. 28,962.00 SQFT				5.50				5.50	159,291
10'X10' SC	CORATIVE CONCRETE, ORE PATTERN, 3000 PSI, 6 WWF (2/H-06)	17,244.00 SQFT				6.25				6.25	107,775
	es BP32B CONCRETE PAVING	& STAMPED				\$267,066					\$267,066
Bid Packages Bi	P32C UNIT PAVING - BRICK PA	AVERS									
32140.001 PAVER BA (3/H-06) ***	SE, 1 BEDDING SAND INCLUDED IN PAVER BASE,	27,488.00 SQFT				0.85				0,85	23,365
32140.003 PAVER BA CONCRET		27,488,00 SQFT				6,00				6.00	164,928

Page 9

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

	44	

Report DOES NOT include Taxes & Insurance or Indirect Costs. Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK 7/9

2:46:44PM	Estima	te file: MARCO ISLANL	VEIERNS P	AKK 2020.0	est - VEI E	KAN'S COM	IMUNITY	PAKK			7/9/2020
item Code	Description	Quantity	Labor	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total Unit S	item Total \$
Bid Packages	BP32C UNIT PAVING - BRICK	PAVERS									
32140.005 (H-103)	PAVER 1-LIGHT 24"X24" RA EXPRESSIONS HXP-20	9,188.00 SQFT				8.00				8.00	73,504
32140.010 (H-104)	PAVER 2-MEDIUM 12"X48" RA EXPRESSIONS HXP-110	396.00 SQFT				8.50				8.50	3,366
	PAVER 3-DARK 8"X24" RA EXPRESSIONS HSP-120	139.00 SQFT				8.50				8.50	1,182
PAVER;	PERMEABLE DRIVEWAY TECHO-BLOC AQUASTORM 5 (5/H06)	14,186.00 SQFT				8.00				8,00	113,488
	TRUNCATED DOME TABLE WARNING PAVERS	99.00 SQFT				9.50				9.50	941
	EXISTING DONATION PAVER ATION (7/H-07)	3,025.00 SQFT				6.00				6.00	18,150
32140.035 CROSS	WALKS, VEHICULAR PAVERS	455,00 SQFT		1 1		8.00				8,00	3,640
Total Bid Pack	ages BP32C UNIT PAVING - BI	RICK PAVERS				\$402,563					\$402,563
						V102,000					4-102,00
	BP32E SYNTHETIC TURF / SU										
TURF (6		13,455.00 SQFT		=		8,50				8,50	114,368
	FOREVERLAWN, 2" CRUSHED GATE (6/H06)	13,455.00 SQFT				3,00				3.00	40,365
NAILEŔ	FOREVERLAWN, COMPOSITE BOARD, MIN. 2"X3" (6/H06)	452.00 LNFT				8.00				8.00	3,616
	PLAYGROUND "NO FAULT CING" SURFACE (7/H06)	4,337.00 SQFT				21.00				21.00	91,077
	PLAYGROUND SURFACING, 4" CK SUB-BASE (7/H06)	4,337.00 SQFT				6.00				6,00	26,022
	PLAYGROUND SURFACING, CONCRETE HEADER CURB	330.00 LNFT				18.00				18.00	5,940
) BOCCE BALL COURT; ERLAWN BOCCEGRASS PLAY (H-07)	718.00 SQFT				11.00				11.00	7,898
) BOCCE BALL COURT; 4" CK (1/H-07)	718.00 SQFT				6.00				6.00	4,308
) BOCCE BALL COURT NAILER (1/H07)	144.00 LNFT				8.00				8.00	1,152

Sort Sequences: 1, Area 2, Bid Packages

7/9/2020

2,016

2,016

\$298,778

35,000

Item

Total \$

3. Not Used

Total

Unit \$

14,00

14,00

10.00

4. Not Used

Report DOES NOT in clude Taxes & Insurance or Indirect Costs. Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK

Other

Costs \$

2:46:44PM	
Item	
Code	

Temp Mati \$ Equipt Rntl \$ Material Equipt Şub Labor \$ Quantity \$

14.00

14.00

\$298,778

10.00

Bid Packages BP32E SYNTHETIC TURF / SURF	ACES
32922,055 (PG-104) BOCCE BALL COURT	144.00 LNFT
CONCRÉTE FOOTER / CONTAINMENT	
CURB 4"X4" (BOCCE BALL COURT -	
1/H07)	
32922,060 (PG-104) BOCCE BALL COURT 6"X12"	144.00 LNFT
HEADER CURR (BOCCE BALL COURT -	

Description

HEADER CURB (BOCCE BALL COURT - 1/H07)
Total Bid Packages BP32E SYNTHETIC TURF / SURFACES

Bid Packages	BP32F CHA	IN LINK FE	ENCE &	GATES	
SEO 100 TEMPO	DADY CENCE	(B O' HT W/		3 500 00 LN	ᆮ

TEMPORARY FENCE (8.0' HT W/ WINDSCREEN)

WINDSCREEN)							
1560.250 TEMPORARY CONSTRUCTION ACCESS (8.0' HT DBL SWING GATES)	2.00 PAIR			850.00		850.00	1,700
Total Bid Packages BP32F CHAIN LINK FENCE	& GATES			\$36,700			\$36,700
Bid Packages BP32H PLANTINGS - SOD - TR	EES - MULCH	1					
32929.005 CD - BERMUDA SOD	176,808.00 SQFT			0.65		0.65	114,925
32939,005 AG - PERENNIAL PEANUT 1 GAL, 12 SPRD	596,00 EACH			5.00		5,00	2,980
32939.010 AW - RED COPPERLEAF — 3 GAL, 24 FULL	181.00 EACH			15.00		15.00	2,715
32939.015 BB - SHADY LADY BLACK OLIVE - 3 CAL, 10' HT	48.00 EACH			600.00		600.00	28,800
32939.025 BW - BUTTERFLY BUSH - 3 GAL, 24 HT	100.00 EACH			35.00		35.00	3,500
32939.030 CR - PITCH APPLE - 3 GAL, 18 FULL	252.00 EACH			30.00		30.00	7,560
32939.035 CS - SILVER BUTTONWOOOD - 2 CAL, 10' HT	20.00 EACH			550,00		550.00	11,000
32939.040 CS2 - RED MAGIC TI PLANT – 3 GAL, 24 HT	47.00 EACH			40.00		40.00	1,880
32939.045 CU - SEA GRADE 7 GAL, 30 FULL	10.00 EACH			45.00		45.00	450
32939.050 CV - CROTON 3 GAL, 14 FULL	69.00 EACH			12.00		12.00	828
32939.055 CV2 - QUEEN EMMA CRINUM LILY - 7 GAL, 30 HT	18.00 EACH			60.00		60.00	1,080
32939,060 DE - GOLD MOUND DURANTA – 3 GAL, 14 SPRD	87.00 EACH			15.00		15.00	1,305
32939.065 DR - ROYAL POINCIANA - 3 CAL, 12' HT	13.00 EACH			275.00		275.00	3,575
32939.070 DT - FLAX LILY - 3 GAL, 12 HT	174,00 EACH			9.00		9.00	1,566

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

	I4P	

Report DOES NOT in clude Taxes & Insurance or Indirect Costs. Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK 7/9

7/9/2020

kem Estimate	E FIIE. INANCO ISLAND		Material	Equipt		N/40/1- 1 1		Other	Total T	11812020
Code Description	Quantity	Labor	\$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total Unit \$	Item Total \$
Bid Packages BP32H PLANTINGS - SOD - TR									01111	171-117
32939.075 EB - SHAGGY DWARF MORNING GLORY - 3 GAL, 14 SPRD	162.00 EACH				20.00				20,00	3,240
32939.080 EG - BLUE DAZE - 1 GAL, 12 SPRD	471.00 EACH				15.00				15.00	7.065
32939.085 FG - GREEN ISLAND FICUS 3 GAL, 24	1,078.00 EACH				9.00				9.00	9,702
32939.090 HF - FIREBUSH - 3 GAL, 14 FULL	25.00 EACH				9.00				9.00	225
32939.095 IN - DWARF RED IXORA - 3 GAL, 16 FULL	117.00 EACH				10.00				10.00	1,170
32939.100 MC - PINK MUHLY GRASS - 1 GAL, 18 HT	198.00 EACH				5.00				5.00	990
32939.110 PA - WHITE LEAVED FOUNTAIN GRASS - 3 GAL, 18 HT	42.00 EACH				9.00				9.00	378
32939.115 PI - PLUMBANGO - 3 GAL, 18 FULL	49,00 EACH				20,00				20.00	980
32939.120 PS - WILD DATE PALM - HEAVY, 12 CT	8.00 EACH				725.00				725.00	5,800
32939.125 PW - WHITE CAPE PLUMBANGO - 3 GAL, 18 FULL	76,00 EACH				20,00				20,00	1,520
32939.130 PX - XANADU PHILODENDRON - 3 GAL, 18 SPRD	499.00 EACH				20.00				20,00	9,980
32939.135 QV - SOUTHERN LIVE OAK - 4 CAL, 16' HT	33.00 EACH				880.00				880.00	29,040
32939.140 RE - FIRECACKER PLANT - 3 GAL, 14 FULL	211.00 EACH				9.00				9,00	1,899
32939.145 RR2 - RELOCATED PALM	9,00 EACH				2,500.00				2,500.00	22,500
32939.150 RH - NEEDLE PALM - 3 GAL, 12 HT	42.00 EACH				125.00				125.00	5,250
32939.155 RR - ROYAL PALM - HEAVY, 10' GW	46,00 EACH				1,900.00				1,900.00	87,400
32939.160 SC - SILVER SAW PALMETTO - 15 GAL, 30 FULL	247.00 EACH				195.00				195.00	48,165
32939,165 SR - BIRD OF PARADICE - 3 GAL, 18 HT	33.00 EACH				60.00				60,00	1,980
32939.170 TD - DWARF FAKANATCHEE GRASS 1 GAL, 18 HT	136.00 EACH				5.00				5.00	680
32939.175 VO2 -WALTER'S VIBURNUM - 3 GAL, 24 FULL	110.00 EACH				15.00				15.00	1,650
32939.180 WB - RELOCATED FOXTAIL PALM	8.00 EACH				2,500.00				2,500.00	20,000
32939.185 ZP - COONTIE - 3 GAL, 24 HT	370,00 EACH				20.00				20.00	7,400
32939.190 MULCH - PINE BARK	52,988.00 SQFT				0.50				0.50	26,494
32939.500 (SF-117) TREE GRATE	3.00 EACH				1,600.00				1,600,00	4,800
Total Bid Packages BP32H PLANTINGS - SOD	- TREES - MULCH				\$480,472					\$480,472
Bid Packages BP32I IRRIGATION					'					-
Did Lackages BL951 WUIGHTION										

Page 12

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

Filtrad	. 51. 44500 101 445							Taxes & Insu	rance or Indire	
2:46:44PM Estimat	te File: MARCO ISLANE	Labor	ARK 2020.0.	.est - VEI E	Sub	Temp	Equipt	Other	Total	7/9/2020 Item
Code Description	Quantity	\$	\$	\$	\$	Matl \$	Rnti \$	Costs \$	Unit \$	Total \$
Bid Packages BP32I IRRIGATION										
32939,195 IRRIGATION SYSTEM	223,125.00 SQFT				0.50				0.50	111,56
32939,200 IRRIGATION WELL & PUMP	1.00 LSUM				15,000.00				15,000.00	15,00
Total Bid Packages BP32I IRRIGATION					\$126,563					\$126,56
Bid Packages BP32M BOARDWALKS										
32001.005 IPE BOARDWALK	4,901.00 SQFT				115.00				115.00	563,61
Total Bid Packages BP32M BOARDWALKS					\$563,615					\$563,61
Bid Packages BP33A WATER UTILITY DISTR	RIBUTION									
33110.150 WATER: CONNECT TO EXISTING WATER LINE	1.00 EACH				2,600.00				2,600.00	2,600
3110,160 WATER: GATE VALVE	1.00 EACH				2,700.00				2,700.00	2,70
33110.170 WATER: <= 10" DUCTILE IRON	550.00 LNFT				50.00				50,00	27,50
33112.150 FIRE WATER: FIRE HYDRANT	2,00 EACH				4,500.00				4,500.00	9,00
33112.160 FIRE WATER: DOUBLE DETECTOR CHECK VALVE	1.00 EACH				2,400.00				2,400.00	2,40
33112,170 FIRE WATER: <= 6" DUCTILE IRON	550,00 LNFT				30,00				30,00	16,50
33112.180 FIRE WATER: PIV <= 6"	1.00 EACH				1,700.00				1,700.00	1,70
33112.190 FIRE WATER: IN-LINE CHECK VALVE	1,00 EACH				2,400.00				2,400.00	2,40
Total Bid Packages BP33A WATER UTILITY D	ISTRIBUTION				\$64,800					\$64,80
Bid Packages BP33B SANITARY UTILITY SE	WERAGE									
3300.150 SANITARY: TIE-IN TO EXISTING MANHOLES	2.00 EACH				7,800.00				7,800.00	15,60
33300.160 SANITARY: <= 8" SDR	275,00 LNFT				80,00				80.00	22,00
Total Bid Packages BP33B SANITARY UTILIT	Y SEWERAGE				\$37,600					\$37,60
Bid Packages BP33C STORM UTILITY DRAIN	NAGE									
33400,000 12 HDPE	227.00 LNFT				45.00				45.00	10,21
33400.005 18 HDPE	4,490,00 LNFT				55,00				55.00	246,95
33400.010 24 HDPE	100.00 LNFT				65.00				65,00	6,50
33400.015 8 HDPE	528.00 LNFT				30.00				30,00	15,84
3400.020 DRAINAGE FLUME	14.00 SQYD				45.00				45.00	63
33400.025 EXIST DRAINAGE INLET TO BE RAISED (C-05)	1.00 EACH				2,500.00				2,500.00	2,50
3400.030 FDOT TYPE C INLET	16.00 EACH				2,200.00				2,200.00	35,20
33400.035 FDOT TYPE C INLET, MODIFIED (CONTROL STRUCTURE W/ SKIMMER)	1.00 EACH				3,200.00				3,200.00	3,20

Sort Sequences: 1. Area
2. Bid Packages
3. Not Used
4. Not Used

Report DOES NOT include Taxes & Incurance or Indirect Costs

:46:44PM	ate File: MARCO ISLAND	VETERNS F	ARK 2020.0	.est - VETI					ance or Indirec	7/9/20
Item		Labor	Material	Equipt	Sub	Temp	Equipt	Other	Total	item
Code Description	Quantity	\$	\$	\$	\$	Mati \$	Rntl \$	Costs \$	Unit \$	Total \$
Bid Packages BP33C STORM UTILITY DRA	INAGE									
3400.040 FDOT TYPE D INLET	1.00 EACH				2,800.00				2,800.00	2,8
3400.045 FDOT TYPE D INLET, MODIFIED (CONTROL STRUCTURE W/ SKIMMER)	2.00 EACH				3,800.00	-			3,800.00	7,0
400.050 MES, 18	2.00 EACH				1,200.00	1			1,200.00	2,4
400.055 SEAWALL OUTFALL	2.00 EACH				3,000.00	1			3,000.00	6,
1400,060 YARD DRAIN, 18	40.00 EACH				2,100.00				2,100,00	84,0
Total Bid Packages BP33C STORM UTILITY					\$423,835				7	\$423,
il Area 001 PARK					\$6,060,514					\$6,060,
					1 1			1		
					1 1					

Sort Sequences: 1, Area 2, Bid Packages 3, Not Used 4, Not Used

Report DOES NOT include Taxes & Insurance or Indirect Costs.

46:44PM	Езиписе	File: MARCO ISLAND						AIVI			7/9/20
Item Code	Description	Quantity	Labor \$	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rnti \$	Other Costs \$	Total Unit \$	Item Total \$
ea 010 RESTRO	OMS										
Bid Packages FINISH / CRAN	BP03A CONCRETE (FORM / REIES)	BAR / PLACE &									
	ETE; COLUMN FTG @ EXT CMU RS (2-EACH)	1.00 CUYD				650.00				650.00	6
	ETE: PERIMETER WALL IG (160 LNFT)	17.78 CUYD				285.00				285.00	5,0
	ETE: THICKENED SLAB FTG @ IU / PAVERS (8 LNFT)	1.00 CUYD				215.00				215,00	2
3310,020 CONCRI	ETE: MUD SLAB @ EXT S (1244 SQFT	19,00 CUYD				395.00				395.00	7,5
	ETE: SLAB ON GRADE <=6" TK	21.00 CUYD				415.00				415.00	8,7
3310.055 CONCR	ETE: THICKENED SLAB FTG @ ALLS (79 LNFT)	4.85 CUYD				215.00				215.00	1,0
	ages BP03A CONCRETE (FORM	/ REBAR / PLACE &				\$23,195					\$23,1
Bid Packages	BP04A CMU MASONRY & PRE-	CAST COPINGS									
4220.310 CMU: EX	XTERIOR WALL	1,458.00 SQFT				22.00				22.00	32,0
	XTERIOR STEM WALL (BELOW 2-COURSE)	211.47 SQFT				22.00				22.00	4,6
4220,315 CMU: EX	XTERIOR SCREEN WALL	73.00 SQFT				22.00			1	22.00	1,6
4220.330 CMU: CC	OLUMNS (2 EACH)	66,00 SQFT				35.00				35.00	2,3
4220.450 CMU: IN	ITERIOR WALL	712.00 SQFT				22.00				22.00	15,6
4225.500 CMU: PC LNFT)	OURED CONCRETE BOND (245	8.05 CUYD				385.00				385,00	3,0
	ages BP04A CMU MASONRY & F	PRE-CAST COPINGS				\$59,408				1	\$59,4
Bid Packages	BP06A ROUGH CARPENTRY - E	LOCKING									
	TRUSSES (BASED ON FLT SQFT OF FLOOR SPACE)	1,734.00 SQFT				4.50				4,50	7,8
KD9 5/8" CD ON 5/12	(ROOF SHEATHING (BASED PITCH)	2,258.00 SQFT				1.85				1.85	4,1
	ages BP06A ROUGH CARPENTR	Y - BLOCKING				\$11,980				1	\$11,9
Bid Packages	BP06C FINISH CARPENTRY - W	OOD TRIM									
6210.050 WOOD T	TRIM @ EXTERIOR (RUNNING	775.00 LNFT				18.00				18.00	13,9
	ages BP06C FINISH CARPENTRY	- WOOD TRIM				\$13,950				-	\$13,9
							- 1				

Page 15

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

Other Costs \$ Unit \$ 65.00	.,
Costs \$ Unit \$ 65.00	1,30 2,14
65.00 165.00	1,30
165,00	2,14
165,00	2,14
	\$3,44
	1
2.75	3,59
	\$3,58
26.00	58,70
1.00	2,2!
	\$60,96
12.00	9,27
	\$9,27
1,600,00	6,40
	\$6,40
475,00	95
	\$95
10,000.00	10,00
	1,600.00 475.00

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

2.4		

Report DOES NOT include Taxes & Insurance or Indirect Costs. Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK 7/9

	e file: MARCO ISLANL	VEIERNS	AKK 2020.0	est - VEIE	KAN 5 COM	MUNITY	PARK			7/9/202
Item Code Description	Quantity	Labor	Material S	Equipt	Sub \$	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total Unit \$	item Total A
Total Bid Packages BP08E OVERHEAD & COI						ume 4	MILL	COSIS #	Unit \$	Total \$
					\$10,000					\$10,00
Bid Packages BP09A STUCCO										
9200,001 EXTERIOR STUCCO OVER CMU	1,563.00 SQFT				18.00				18.00	28,134
9200.002 EIFS BAND EXTERIOR	175.00 LNFT				9.00				9,00	1,57
9200.005 CEILING SYNTHETIC STUCCO	976.00 SQFT				16.00				16.00	15,610
Total Bid Packages BP09A STUCCO					\$45,325					\$45,32
Bid Packages BP09B DRYWALL & METAL FF	RAMING									
9210.005 DRYWALL FRAMED CEILING SYSTEM	976.00 SQFT				7.50				7.50	7,32
9210.010 FURRED GYPBOARD WALLS @ CHASE WALL	660.00 SQFT				7.50				7.50	4,95
Total Bid Packages BP09B DRYWALL & META	AL FRAMING				\$12,270					\$12,27
Bid Packages BP09I PAINTING & COATINGS										
9910,005 CMU INTERIOR BLOCK FILL & PAINT	2,790.00 SQFT				0.95				0.95	2,65
9910,010 GYPBOARD INTERIOR WALLS	1,636.00 SQFT				0.95				0.95	1,55
9910,015 STUCCO EXTERIOR PAINT	1,563.00 SQFT				0.95				0.95	1,48
9910.020 PAINT DOORS / FRAMES	4.00 EACH				250.00				250.00	1,00
9939.900 SEALED CONCRETE FLOORS	976.00 SQFT				1.25				1,25	1,22
Total Bid Packages BP09I PAINTING & COATI	NGS				\$7,910					\$7,91
Bid Packages BP10A DIV 10 SPECIALTIES: T	LT PARTITION &									
ACCESS / MISC SPECIALTIES										
0280.000 36" GRAB BAR	3,00 EACH				200,00				200.00	600
0280.000 42" GRAB BAR	6.00 EACH				200,00			1	200.00	1,200
0280.000 BABY CHANGING STATIOM	2.00 EACH				400.00			11	400.00	806
0280,000 HAND DRYER	7.00 EACH				1,500.00				1,500.00	10,500
10280,000 HYGIENE DISPENSER 10280,000 MIRROR	1.00 EACH 8.00 EACH				450.00 300.00				450.00	45
0280.000 PAPER TOWEL/WASTE RECEPTACLE	4.00 EACH				800.00				300.00	2,40
0280,000 PAPER TOWEDWASTE RECEPTAGEE	7.00 EACH				150.00			1	800.00	3,20
0280.000 SOAP DISP	8.00 EACH				150.00				150,00 150,00	1,05 1,20
0280,000 SS BR PARTITION	8.00 EACH				1,275.00				1,275.00	10,20
0280,000 SS BR URINAL SCREEN	2.00 EACH				750.00				750.00	1,50
10280.000 TOILET PAPER HOLDER	10.00 EACH				75,00				75.00	75
Total Bid Packages BP10A DIV 10 SPECIALTII	ES: TLT PARTITION				\$33,850			1		\$33,85
& ACCESS / MISC SPECIALTIES					400,000					400,00
Bid Packages BP10E SIGNAGE / IDENTIFYIN										
10140.000 SIGNAGE ALLOWANCE	1.00 ALLW				1,500.00				1,500.00	1,50

Sort Sequences: 1. Area
2. Bid Packages
3. Not Used
4. Not Used

Report DOES NOT include Taxes & Insurance or Indirect Costs.

Item			Labor	Material	Equipt	Sub	Temp	Equipt	Other	Total	Item
Code	Description	Quantity	\$	\$	\$	\$	Matt \$	Rnti\$	Costs \$	Unit \$	Total \$
Total Bid Packa	ges BP10E SIGNAGE / IDENT	TEYING DEVICES				\$1,500					\$1,50
Bid Packages B	P10G LOUVERS / VENTS										
8900.090 WINDOW		3.00 EACH		1 1		75.00				75.00	22
Total Bid Packa	ges BP10G LOUVERS / VENT	s				\$225					\$22
Bid Packages B	P101 FIRE EXTINGUISHER /	CABINETS									
	DUNTED FIRE EXTINGUISHER	2.00 EACH		1 1		400.00				400.00	80
Total Bid Packa	ges BP101 FIRE EXTINGUISH	ER / CABINETS				\$800					\$80
Bid Packages B	P21A FIRE SUPPRESSION										
1000,000 FIRE SPR		1,016.00 SQFT				2.25				2.25	2,28
Total Bid Packa	ges BP21A FIRE SUPPRESSI	ON				\$2,286					\$2,28
Bid Packages B	P22A PLUMBING										
22000.000 PLUMBIN		22,00 EACH				2,300.00				2,300.00	50,60
22000.001 BI-LEVEL	EWC	1.00 EACH									
2 2000.001 LAV -2 2 2000.001 LAV -WH-	ADA	3,00 EACH 5,00 EACH									
22000.001 LAV -WH- 22000.001 MOP SINI		1.00 EACH		1							
2000.001 PLUMBIN		1.00 EACH				3,000.00				3,000,00	3,00
2000.001 UR - WH	w/FV	2.00 EACH				.,				.,	-,
22000.001 WC / FM v	w/FV & OF SEAT	7,00 EACH									
22000,001 WC ADA		3.00 EACH		h I							
22000.100 PLUMBIN		1,016.00 SQFT				4.75				4.75	4,82
	G AG SAN/DOM WATER	1,016.00 SQFT				5.50				5.50	5,58
Total Bid Packag	ges BP22A PLUMBING					\$64,014					\$64,014
Bid Packages B (HVAC)	P23A HEATING, VENTING &	AIR-CONDITIONING									
23100.100 HVAC AIR RESTRO	R CIRCULATION FOR	1.00 ALLW				16,000.00				16,000.00	16,000
Total Bid Packag	ges BP23A HEATING, VENTII IING (HVAC)	4G &				\$16,000					\$16,00
Bid Packages B	P26A ELECTRICAL										
26000.000 ELECTRIC	CAL SERVICE	1,016,00 SQFT				4.50				4.50	4,57
	CAL LIGHT FIXTURES	1,016.00 SQFT				2.00				2.00	2,03
	ges BP26A ELECTRICAL					\$6,604					\$6,60
tal Area 010 REST	TROOMS					\$393,904					\$393,90

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

									axes & insur	ance or Indire	et Costs.
2:46:44PM	Estimate	File: MARCO ISLAND	VETERNS P	ARK 2020.0	est - VETE	RAN'S COM	IMUNITY I	PARK			7/9/202
Item Code	Description	Quantity	Labor \$	Material	Equipt \$	Sub \$	Temp Mati \$	Equipt Rnti \$	Other Costs \$	Total Unit \$	Item Total \$
rea 020 BAND	STAND										
Bid Package FINISH / CRA	s BP03A CONCRETE (FORM / REI	BAR / PLACE &									
3310,005 CONC	RETE: COLUMN FTG 6.0'SQ X	27.00 CUYD				385.00				385.00	10,39
3310.007 CONC (8-EAC	RETE: PIER 3.75' SQ X 3.0' HIGH CH)	12.50 CUYD				850.00				850.00	10,62
FOOT	RETE: PERIMETER WALL ING (533 LNFT)	49,35 CUYD				285.00				285.00	14,0
(264 L	•	24.00 CUYD				285.00				285.00	6,84
	RETE: WALL FTG @ CONCRETE WALLS (170 LNFT)	19.00 CUYD				285.00				285.00	5,4
(5459		101.00 CUYD				415.00				415,00	41,9
	RETE: THICKENED SLAB FTG @ NALLS (185 LNFT)	11.44 CUYD				215.00				215.00	2,4
3310.065 CONC STEPS	RETE: CONCRETE FORMED	155.00 LNFT				8,00				8.00	1,2
	RETE: BAND STAND CTURAL LID (857 SQFT)	21.00 CUYD				28.00				28.00	5
	STAND: SELECT FILL MATERIAL ILL POST STEM WALLS)	697.00 CUYD				21.50				21.50	14,9
Total Bid Pac FINISH / CRA	:kages BP03A CONCRETE (FORM) NES)	/ REBAR / PLACE &				\$108,528					\$108,52
	8 BP04A CMU MASONRY & PRE-C										
	EXTERIOR WALL	1,670.00 SQFT		1		22.00				22.00	36,74
	EXTERIOR STEM WALLS W GRADE)	1,363.00 SQFT				22.00				22.00	29,98
4220.314 CMU: I	EXTERIOR WALL @ 2'-10"	633,00 SQFT		1		22.00				22.00	13,9
4220.330 CMU:	COLUMNS (2-EACH)	60.00 SQFT				35.00				35.00	2,10
	POURED CONCRETE BOND (511 LNFT)	16.78 CUYD				385.00				385.00	6,4
Total Bid Pac	kages BP04A CMU MASONRY & P	PRE-CAST COPINGS				\$89,212					\$89,2
METAL DECI		METAL JOIST -									
	M FRAME SUPER STRUCTURE LL (3-SECTIONS)	77.96 TONS				5,500.00				5,500.00	428,78
	M KICKER SUPPORT STEEL AR TIES 8"X8")	6.61 TONS				5,750.00				5,750.00	38,0

Page 19

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

2.46	 DR A	

Report DOES NOT in clude Taxes & Insurance or Indirect Costs. Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK 7/9.

tem Code Description	Quantity	Labor	Material	Equipt	Sub	Temp Mati \$	Equipt Rntl \$	Other Costs \$	Total	Item
Storiphon		,	*		3	Matu >	POTE \$	Costs \$	Unit \$	Total \$
Bid Packages BP05A STRUCTURAL STEEL -	METAL JOIST -									
METAL DECK	40.40.7010									
5100.135 I-BEAM SUPPORT STEEL (STEEL TO STEEL CONNECT)	10.43 TONS				5,500.00				5,500.00	57,33
5150.115 STRUCTURAL 12" ZEE GIRT FRAMING (FRONT SECTION @ 11'-3" DEEP)	574.00 LNFT				11.50				11,50	6,60
5150.125 STRUCTURAL 12" ZEE GIRT FRAMING (MIDDLE SECTION @ 11'-4" DEEP)	538,00 LNFT				11.50				11.50	6,18
5150.135 STRUCTURAL 12" ZEE GIRT FRAMING (REAR SECTION @ 11'-2")	485.00 LNFT				11.50				11.50	5,57
5300.115 EPICORE ER6.5A ROOF DECK CEILING SYSTEM	3,053.00 SQFT				37.50				37.50	114,48
Total Bid Packages BP05A STRUCTURAL STE METAL DECK	EL - METAL JOIST -				\$656,978					\$656,97
Bid Packages BP05C METAL FABRICATIONS										
5510.115 EXTERIOR WALL RAILINGS	204.00 LNFT				45.00			1	45.00	9,18
5730.000 SS RAMP RAILING	186.00 LNFT				145.00				145.00	26,97
Total Bid Packages BP05C METAL FABRICATION	ONS				\$36,150					\$36,15
Bid Packages BP07A DAMPPROOFING - WATE	ERPROOFING -									
7100.005 CAULKING (BASED ON SQFT OF STRUCTURE)	4,000.00 SQFT				0.95				0.95	3,80
Total Bid Packages BP07A DAMPPROOFING - JOINT SEALANTS	NATERPROOFING -				\$3,800					\$3,80
Bid Packages BP07C METAL ROOF PANELS										
5150.170 5/8" CDX ROOF SHEATHING	3,053.00 SQFT				2.00			1	2.00	6,10
7410.150 PETERSON ALUM METAL ROOFING TITE-LOC PLUS .032 ~ 2" HIGH SEAMS	3,053.00 SQFT				26.00				26.00	79,37
7440.150 FRONT FACE INFILL OF STEEL BEAM: ALUM METAL FASCIA	3,090.00 SQFT				24.00				24,00	74,16
7580.011 90-LB PEEL & STICK	3,053.00 SQFT				1.00			1	1.00	3,05
Total Bid Packages BP07C METAL ROOF PANE	ELS				\$162,697					\$162,69
Bid Packages BP07E MEMBRANE ROOFING										
7500.172 60 MIL TPO FULLY ADHERED OVER R20 INSULATION	857.00 SQFT				18.00				18.00	15,42
Total Bid Packages BP07E MEMBRANE ROOF	NG				\$15,426					\$15,42
			20							

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

Report DOES NOT include Taxes & Insurance or Indirect Costs.

2:46:44PM	Estimat	e File: MARCO ISLAND	VETERNS F	PARK 2020.0.	est - VETE					ance of ilidited	7/9/2020
Item			Labor	Material	Equipt	Sub	Temp	Equipt	Other	Total	Item
Code	Description	Quantity	\$	\$	\$	\$	Mati \$	Rnt \$	Costs \$	Unit \$	Total \$
HARDWA	iges BP08A HM DOORS / HM FRAM RE & INSTALLATION										
W	FRAME AND HM DOOR HARDWARE	6,00 EACH				1,600,00				1,600.00	9,600
	Packages BP08A HM DOORS / HM F HARDWARE & INSTALLATION	RAMES / WOOD				\$9,600					\$9,600
GLASS &											
	(ED ALUMINUM WINDOWS - 2'X2'	5,00 EACH				520.00				520.00	2,600
	Packages B P0 8B ENTRANCES / STO S / GLASS & GLAZING	DREFRONTS /				\$2,600					\$2,600
Bid Packa	iges BP09A STUCCO										
	NTHETIC STUCCO CEILINGS	701.00 SQFT				16.00				16.00	11,216
WA	UCCO OVER CMU EXTERIOR ALLS	4,112.00 SQFT				18.00				18.00	74,016
Total Bid F	Packages BP09A STUCCO					\$85,232					\$85,232
Bid Packa	iges BP09B DRYWALL & METAL FR										
9210.015 DR	YWALL/FRAMED CEILINGS	536.00 SQFT				7.50				7.50	4,020
	RR CMU WALL W/ GYP BOARD	203.00 SQFT				7.50			1	7.50	1,523
Total Bid F	Packages BP09B DRYWALL & META	AL FRAMING				\$5,543					\$5,543
Bid Packa	ges BP09C ACOUSTICAL / ACOUS	TICAL CEILINGS									
	OATING ACOUSTICAL CLOUDS / OUSTICAL PANELS	1,760,00 SQFT				18.00				18.00	31,680
Total Bid F	Packages BP09C ACOUSTICAL / AC	OUSTICAL CEILINGS				\$31,680					\$31,680
	ges BP09I PAINTING & COATINGS										
9910,020 PA	INT DOORS / FRAMES	6.00 EACH				400.00	0			400.00	2,400
	IU INTERIOR BLOCK FILL & PAINT	2,934.00 SQFT				3.00				3.00	8,802
	TERIOR PAINT ON GYPSUM	203,00 SQFT		1 1		2,25			1	2.25	457
	TERIOR PAINT ON STUCCO	2,696.00 SQFT		1 1		3.00				3.00	8,088
	UCCO AT CMU SIDEWALK WALLS	2,118.00 SQFT				3.00				3.00	6,354
	DERSIDE OF EPICORE ROOF DECK	N/A		1 1						277	
	INT EXPOSED STRUCTURAL STEEL	6,256.00 SQFT				6.00	·			6.00	37,536
	INT RAILINGS	279,00 LNFT				8,00				8.00	2,232
	ALED CONCRETE FLOORS Packages BP09I PAINTING & COATI	2,724,00 SQFT				2.00				2.00	5,448
TOTAL BIOL	rackayes Drust PAINTING & COATI	1100				\$71,317					\$71,317

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

Report DOES NOT include Taxes & Insurance or Indirect Costs.

COMMUNITY PARK 7/9

Λ.	46	. A .	2	8.4

Estimate File: MARCO ISLAND VETERNS PARK 2020.0.6

2:46:44PM	Estimate	e File: MARCO ISLAND	ND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK								7/9/2020	
Item			Labor	Material	Equipt	Sub	Temp	Equipt	Other	Total	item	
Code	Description	Quantity	\$	\$	\$	\$	Mati \$	Rnti\$	Costs \$	Unit \$	Total \$	
	ages BP10A DIV 10 SPECIALTIES: T	LT PARTITION &										
ACCESS	/ MISC SPECIALTIES											
10280.000 36	GRAB BAR	2.00 EACH				200.00				200.00	400	
10280.000 42		2.00 EACH				200.00				200.00	400	
10280,000 BA	ABY CHANGING STATIOM	2.00 EACH				400.00				400,00	800	
10280.000 HA		2.00 EACH				1,500.00				1,500.00	3,000	
10280.000 Mil		2,00 EACH		1		300,00				300.00	600	
	APER TOWEL/WASTE RECEPTACLE	2.00 EACH				800.00				800.00	1,600	
	ANITARY NAPKIN DISP	1.00 EACH				150.00				150,00	150	
10280,000 SC	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2.00 EACH				150.00				150.00	300	
	DILET PAPER HOLDER	2.00 EACH				75.00				75.00	150	
	Packages BP10A DIV 10 SPECIALTIE S / MISC SPECIALTIES	ES: TLT PARTITION				\$7,400					\$7,400	
	ages BP10E SIGNAGE / IDENTIFYING											
	GNAGE ALLOWANCE	1.00 ALLW				3,500,00				3,500.00	3,500	
Total Bid	Packages BP10E SIGNAGE / IDENTIF	YING DEVICES				\$3,500					\$3,500	
Bid Packa	ages BP10G LOUVERS / VENTS											
1W 000.0008	INDOW LOUVERS	8.00 EACH				225.00				225.00	1,800	
10210.115 WI	IND DRIVEN RAIN LOUVER	331.00 SQFT				245.00				245.00	81,095	
	OUVER SCREEN WALL @ BOH ROOF	146.00 SQFT				45.00				45,00	6,570	
	-2" HT) Packages BP10G LOUVERS / VENTS										.,	
TOTAL DIGI	Packages BF100 LOUVERS / VEN13					\$89,465					\$89,465	
	ages BP101 FIRE EXTINGUISHER / C											
	ALL MOUNTED FIRE EXTINGUISHER	2.00 EACH				400.00				400.00	800	
Total Bid	Packages BP101 FIRE EXTINGUISHE	R/CABINETS				\$800					\$800	
	ages BP11E PROJECTION SCREENS	- AUDIO-VISUAL										
EQUIPME	AGE EQUIP - PROJECTION SCREEN	1.00 ALLW				45 000 00						
		.,				15,000.00				15,000.00	15,000	
	Packages BP11E PROJECTION SCRI	EEN2.				\$15,000					\$15,000	
AUDIO-VIS	SUAL EQUIPMENT											
Bld Packa	eges BP21A FIRE SUPPRESSION											
21000.000 FIF	RE SPRINKLER SYSTEM	5,500,00 SQFT				4,00				4.00	22,000	
Total Bid I	Packages BP21A FIRE SUPPRESSIO	N				\$22,000					\$22,000	
Bid Packa	eges BP22A PLUMBING											
22000.000 PL	UMBING FIXTURES	4.00 EACH				2,300.00				2,300.00	9,200	
										7	-,	

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used

2-46-44PM

Report DOES NOT include Taxes & Insurance or Indirect Costs. Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK 7//

2:46:44PM	Estimate Fil	e: MARCO ISLANI	D VETERNS F	PARK 2020.0	.est - VETE	ERAN'S COM	IMUNITY	PARK			7/9/2020
item Code	Description	Quantity	Labor \$	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rnti \$	Other Costs \$	Total Unit \$	Item Total \$
Bid Packag	es BP22A PLUMBING										
22000,001 LAV		2.00 EACH									
22000,001 WC-	ADA	2.00 EACH									
22000.100 PLUI	MBING UG SANITARY	1,500.00 SQ FT				4.75				4.75	7,125
	MBING AG SAN/DOM WATER	1,500.00 SQFT				5.50				5.50	8,250
Total Bid Pa	ckages BP22A PLUMBING					\$24,575					\$24,575
Bid Packag (HVAC)	es BP23A HEATING, VENTING & AIR-	CONDITIONING									
	C: GREENROOM & RESTROOMS	5,500.00 SQFT				3.50				3,50	19,250
	ckages BP23A HEATING, VENTING &					\$19,250					\$19,250
	TIONING (HVAC)										
	es BP26A ELECTRICAL										
	CTRICAL SERVICE	5,500.00 SQFT				4.50				4.50	24,760
	CTRICAL LIGHT FIXTURES	5,500.00 SQFT				2.00				2.00	11,000
Total Bid Pa	ckages BP26A ELECTRICAL					\$35,750					\$35,760
Bid Packag CAISSONS	es BP31F SPECIAL FOUNDATIONS: F	ILES /									
31620.005 MOB	ILIZATION	1.00 LSUM				12,500.00				12,500.00	12,500
	CAST PRESTRESSED CONCRETE S <=16" DIAM. (8-CAPS W/ 4-PER	1,280.00 LNFT				65.00				65.00	83,200
31620.750 PILE REQ	LOAD TEST (IF A PILE LOAD IS UIRED ADD \$30.000)	N/A									
CAISSONS	ickages BP31F SPECIAL FOUNDATION	NS: PILES /				\$95,700					\$95,700
Total Area 020 l	BAND STAND					\$1,592,202					\$1,592,202

Sort Sequences: 1. Area 2. Bid Packages 3. Not Used 4. Not Used


Report DOES NOT include Taxes & Insurance or Indirect Costs.


2:46:44PM	Estimate File: MARCO ISLAND VETERNS PARK 2020.0.est - VETERAN'S COMMUNITY PARK										7/9/2020
Item Code	Description	Quantity	Labor \$	Material \$	Equipt \$	Sub \$	Temp Mati \$	Equipt Rnt \$	Other Costs \$	Total Unit \$	Item Total \$
ESTIMATE T	OTALS		I.			\$0.046.60C					\$8,046,620



PROJECT SCHEDULE










VALUE ENGINEERING LOG





Version: 002

Manhattan
Bullding exertence.
MARCO ISLAND VETERAN'S COMMUNITY PARK MARCO ISLAND, FL Date: JULY 30, 2020



Builder-Driven Preconstruction

			Order of	Owner			
en No.	Item Description	Date Initiated	Magnitude Priolog	Approval Code	Action By:	Required Complete Date	Comments
	CIVIL, HARDSCAPE & LANDSCAPING						
HS1	Bid Peckage 12E Site Furnishings reduction in specified manufacturers and alternate manufacturers	13-Jul-20	(\$145,730)	Approved			
HSZ	in lieu of Permeable (H-106) Hardscape Psvers (BP32C) replace with Sod	13-Jul-20	(\$229,991)	Approved			
HS3	in lieu of 6" crushed concrete, substitute with a 3"-4" alternate sub-base	13-Jul-20	(\$31,203)	Approved			
HS4	Reduction in quantity of BP32E Synthetic Turf / Surfaces; replace with	13-Jul-20	(\$39,850)	Approved			
HB5	Landscape / Sod Modify the extent of IPE Boardwalk (I.E. Central Core) (I.E. Behind Back of						
прэ	Bland Stend) CIVIL, HARDSCAPE & LANDSCAPING TOTAL	13-Jul-20	(\$118,042)	Approved	TOTA	L ACCEPTED:	-\$564,83
	(Order of Magnitude Pricing)					L REJECTED:	
					тот	AL PENDING:	
	STRUCTURAL						
81	Enter description on detail sheet	9-Jan-19					
	STRUCTURAL TOTALS				TOTA	L ACCEPTED:	
	(Order of Magnitude Pricing)					L REJECTED:	
					тот	AL PENDING:	
	EXTERIOR ENVELORE						
EXT1	Enter description on detail sheet	9-Jan-19					
	EXTERIOR ENVELOPE TOTALS					L ACCEPTED:	
	(Order of Magnitude Pricing)					L REJECTED:	
					101	AL PENDING:	
	INTERIOR Enter description on detail sheet						
INTS	INTERIOR TOTALS	9-Jan-19			TOTA	L ACCEPTED:	
	(Order of Magnitude Pricing)		-			L REJECTED:	
	(Graci or magnitado Frienig)		1			AL PENDING:	
	MECHANICAL						
111	Enter description on detail sheet	9-Jan-19					
	MECHANICAL TOTALS				TOTA	L ACCEPTED:	
	(Order of Magnitude Pricing)				TOTA	L REJECTED:	
					тот	AL PENDING:	
	ELECTRICAL				-		
560	Add power bollards (Outlets) throughout the park. Allow for 12-each.	30-Jul-20	\$36,433	Approved			
E2:	Increase Allowance for Sita Lighting	30-Jul-20	\$30,361	Approved		N. N. D.	
	Do Not Use This Line						
	ELECTRICAL TOTALS				TOTA	L ACCEPTED:	\$66,79
	(Order of Magnitude Pricing)					L REJECTED:	
					TOT	AL PENDING:	
	GENERAL MULTI BID PACKAGE					,,	
G1	Substitute Band Stand structure with a Fabric Shade structure	13-Jul-20	(\$847,113)	Rejected			
62	Total Trails Redesign for Savings	13-Jul-20	(\$191,818)	Approved		Sc II.M	
	OTHER TOTALS					L ACCEPTED:	-\$191,81
	(Order of Magnitude Pricing)				TOTA	L REJECTED:	-\$847,11
					тот	AL PENDING:	
	PROJECT TOTALS:			CUE	DENT BUD	SET AMOUNT	\$9,524,18
	PROJECT TOTALS:			COR	TATE OF THE PARTY	L ACCEPTED	-\$689,85
	REVISED TOTAL WITH AC	CEDTED VA	LIE MANAGE	WENT			\$8,834,33
	RESIDED I VIAL WITH AC	VERIED VA	LUE MANAGE	WEIVI	TOT	AL PENDING	ψ0,004,00
	REVISED TOTAL WITH PE	NDING VA	HE MANAGEM	ENT			\$8,834,33
	ALTIGED I GIAL WITH PE		maingem	-341	TOTA	L REJECTED	-5847,113
u tudice*	ed are order of magnifude only. Value Management cost items	most he income	cuted into the drawl-	ore and specifi			75 NW10
	variety and the second control of the					sed on revised	Not all VIII Items can be accepted where

MARCO ISLAND, FL

Date: JULY 30, 2020

Civil, Hardscape & Landscaping - Value Management Detail

ITEM NO.

HS1

Bid Package 12E Site Furnishings reduction in specified manufacturers and alternate manufacturers





A = Add D = Deduct

ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
					\$0
D	Target Projection in Savings	1	LSUM	\$120,000.00	(\$120,000
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
	Add Services from Design team to redraw				\$0
	Design Completion Contingency				\$0
o Not Use This Line					
					(\$120,000)
Date Generated	13-Jul-20	Escalation		0.000%	\$0
Status	Approved	Sub Default Insu	ırance	1.500%	(\$1,800)
Comments		Design Continge	ency	7.000%	(\$9,987)
		MCF Contingen	су	3.000%	(\$3,654)
		Fee		5.000%	(\$7,234)
		IT, Scheduling 8	PROCOR	0.242%	(\$328)
		Insurance		1.175%	(\$1,680)
		P&P Bonds		0.732%	(\$1,047)

MARCO ISLAND, FL Date: JULY 30, 2020

Civil, Hardscape & Landscaping - Value Management Detail

ITEM NO.

HS2 In lieu of Permeable (H-106) Hardscape Pavers (BP32C) replace with Sod





A = Add D = Deduct

ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
					\$0
D	Remove Paver Base	14,186	SQFT	\$0.85	(\$12,058
D	Remove Sand Bed	14,186	SQFT	\$6.00	(\$85,116
D	Remove Paver	14,186	SQFT	\$8.00	(\$113,488
Α	Sod	14,186	SQFT	\$1.50	\$21,279
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
	Add Services from Design team to redraw				\$0
	Design Completion Contingency				
o Not Use This Line					\$0
O NOLOSE THIS LINE				-	(\$189,383)
Date Generated	13-Jul-20	Escalation		0.000%	\$0
status	Approved	Sub Default Insu	rance	1.500%	(\$2,841)
comments		Design Continge	ncy	7.000%	(\$15,762)
	7	MCF Contingency		3.000%	(\$5,767)
		Fee		5.000%	(\$11,417)
		IT, Scheduling & PROCOR		0.242%	(\$517)
		Insurance		1.175%	(\$2,652)
	I .	P&P Bonds		0.732%	(\$1,652)

MARCO ISLAND, FL

Date: JULY 30, 2020

Civil, Hardscape & Landscaping - Value Management Detail

ITEM NO.

HS3 In lieu of 6" crushed concrete, substitute with a 3"-4" alternate sub-base material





A = Add

ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
					\$0
D	Delete 6" crushed concrete base	12,847	SQFT	\$6.00	(\$77,082
Α	Add for alternate base material	12,847	SQFT	\$4.00	\$51,388
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
	Add Services from Design team to redraw				\$0
	Design Completion Contingency				\$0
Do Not Use This Line					
					(\$25,694)
Date Generated	13-Jul-20	Escalation		0.000%	\$0
Status	Approved	Sub Default Insu	rance	1.500%	(\$385)
Comments		Design Continge		7.000%	(\$2,138)
		MCF Contingend	у	3.000%	(\$782)
		Fee		5.000%	(\$1,549)
		IT, Scheduling &	PROCOR	0.242%	(\$70)
		Insurance		1.175%	(\$360)
		P&P Bonds		0.732%	(\$224)

MARCO ISLAND, FL

Date: JULY 30, 2020

Civil, Hardscape & Landscaping - Value Management Detail

ITEM NO.

HS4 Reduction in quantity of BP32E Synthetic Turf / Surfaces; replace with Landscape / Sod





A = Add D = Deduct

ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
					\$0
D	Reduce quantity to 10k square feet	3,455	SQFT	\$11.50	(\$39,733)
Α	Add back for Landscape / Sod	3,455	SQFT	\$2.00	\$6,910
					\$0
					\$0
					\$0
					\$0
					50
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
	Add Services from Design team to redraw				\$0
	Design Completion Contingency				\$0
Do Not Use This Line	Design Completion Contingency		-		\$0
DO NOT OSE THIS EINC		I			(\$32,823)
Date Generated	13-Jul-20	Escalation		0.000%	\$0
Status	Approved	Sub Default Insu	rance	1.500%	(\$492)
Comments		Design Continge	ncy	7.000%	(\$2,732)
		MCF Contingend	су	3.000%	(\$999)
		Fee		5.000%	(\$1,979)
		IT, Scheduling & PROCOR 0.24		0.242%	(\$90)
				1.175%	(\$460)
		P&P Bonds		0.732%	(\$286)
					(\$39,860)

MARCO ISLAND, FL

Date: JULY 30, 2020

Civil, Hardscape & Landscaping - Value Management Detail

ITEM NO.

HS5 Modify the extent of IPE Boardwalk (I.E. Central Core) (I.E. Behind Back of Band Stand)





A = Add

ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
					\$0
D	IPE Board Walk	900	SQFT	\$115.00	(\$103,500)
Α	Upgraded Concrete Walk	900	SQFT	\$7.00	\$6,300
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
	Add Services from Design team to redraw				\$0
	Design Completion Contingency				\$0
Do Not Use This Line	Design Completion Containgency				\$ 0
					(\$97,200)
Date Generated	13-Jul-20	Escalation		0.000%	\$0
Status	Approved	Sub Default Insu		1.500%	(\$1,458)
Comments		Design Continge		7.000%	(\$8,090)
		MCF Contingend	у	3.000%	(\$2,960)
		Fee		5.000%	(\$5,860)
		IT, Scheduling &	PROCOR	0.242%	(\$265)
		Insurance		1.175%	(\$1,361)
		P&P Bonds		0.732%	(\$848)
					(\$118,042)

MARCO ISLAND, FL

Date: JULY 30, 2020

Electrical - Value Management Detail

ITEM NO.

E1 Add power bollards (Outlets) throughout the park. Allow for 12-each.





A = Add

ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
					\$0
Α	Power Bollard	12	EACH	\$2,500.00	\$30,000
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
	Add Services from Design team to redraw				\$0
					\$0
	Design Completion Contingency				\$0
Do Not Use This Line					
	Too 1 1 00				\$30,000
Date Generated	30-Jul-20	Escalation		0.000%	\$0
Status	Approved	Sub Default Insu		1.500%	\$450
Comments		Design Continge		7.000%	\$2,497
		MCF Contingend	су	3.000%	\$914
		Fee		5.000%	\$1,809
		IT, Scheduling &	IT, Scheduling & PROCOF 0.242%		\$82
		Insurance		1.175%	\$420
		P&P Bonds		0.732%	\$262
	·				\$36,433

MARCO ISLAND, FL Date: JULY 30, 2020

Electrical - Value Management Detail

ITEM NO.

E2 Increase Allowance for Site Lighting





A = Add

ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
					\$0
Α	Increase Site Lighting Allowance	1	ALLW	\$25,000.00	\$25,000
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
					\$0
	Add Services from Design team to redraw				\$0
	Design Completion Contingency				\$0
Do Not Use This Line					
					\$25,000
Date Generated	30-Jul-20	Escalation		0.000%	\$0
Status	Approved	Sub Default Insu		1.500%	\$375
Comments		Design Continge		7.000%	\$2,081
		MCF Contingend	у	3.000%	\$761
		Fee		5.000%	\$1,507
		IT, Scheduling &	PROCOF	0.242%	\$68
		Insurance		1.175%	\$350
		P&P Bonds		0.732%	\$218
					\$30,361

MARCO ISLAND, FL Date: JULY 30, 2020

General Multi Bid Package - Value Management Detail

ITEM NO.

G1 Substitute Band Stand structure with a Fabric Shade structure





A = Add

D Concrete Column Fig 6.0" say 2.5" dp 27 CUYD \$385.00 (\$10,395 D Concrete Piers 7.5" say x 3.0" ht 13 CUYD \$850.00 (\$428,780 D Steel Fleam Super Structure 30" tall (3-sections) 78 TONS \$5,500.00 (\$428,780 D Steel Fleam Super Structure 30" tall (3-sections) 7 TONS \$5,500.00 (\$428,780 D Steel Fleam Kicker Support Steel (Collar Ties) 7 TONS \$5,500.00 (\$428,780 D Steel Fleam Support Steel (Steel to Steel Connect) 10 TONS \$5,500.00 (\$47,383 D Steel Fleam Support Steel (Steel to Steel Connect) 10 TONS \$5,500.00 (\$47,383 D Steel Fleam Support Steel (Steel to Steel Connect) 10 TONS \$5,500.00 (\$47,383 D Steel Fleam Support Steel (Steel to Steel Connect) 10 TONS \$5,500.00 (\$47,383 D Fleam Steel Fleam Support Steel (Steel to Steel Connect) 10 TONS \$5,500.00 (\$47,383 D Fleam Steel Fleam Fla	D	ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
D	D						\$0
D Concrete Pier 3.75° sq x 3.0° ht D Steel I-Beam Super Structure 30" tall (3-sections) D Steel I-Beam Kicker Support Steel (Collar Ties) T TONS S \$5,500.00 (\$428,780 D Steel I-Beam Kicker Support Steel (Collar Ties) T TONS S \$5,500.00 (\$428,780 D Steel I-Beam Kicker Support Steel (Collar Ties) T TONS S \$5,500.00 (\$428,780 D Steel Structural 12" Zee Girt Framing S 1,597 LNFT S 11.50 (\$18,366 D Steel Structural 12" Zee Girt Framing S 3,053 SQFT S 11.50 (\$18,366 D Epicore ER6.5 Roof Deck Ceiling S 3,053 SQFT S 2.00 (\$6,106 D Peterson Alum Metal Roofing D Front Face Infill of Steel Beam: Alum Fascia S 3,093 SQFT S 2.00 (\$79,378 D Front Face Infill of Steel Beam: Alum Fascia S 3,093 SQFT S 2.00 (\$74,160 D 90-lb Peel & Stick S 3,053 SQFT S 2.00 (\$74,160 D 90-lb Peel & Stick S 3,053 SQFT S 2.00 (\$74,160 D 90-lb Peel & Stick S 3,053 SQFT S 2.00 (\$74,160 S 3,053 SQFT S 2.00 (\$15,050 D 90-lb Peel & Stick S 3,053 SQFT S 2.00 (\$15,050 D Floating Acoustical Clouds / Panels D Wind Driven Rain Louver S 31 SQFT S 2.00 (\$15,050 D Stage Equip: Projection Screens 1,760 SQFT S 18.00 (\$15,050 D Fire Sprinkler: Band Stand Area Only 4,643 SQFT S 2.50 (\$15,050 D Electrical: Band Stand Area Only 4,643 SQFT S 2.50 (\$25,537 D D Deep Foundations: Piles 1 LSUM \$63,700.00 (\$63,700.00 A Deep Foundations: Piles (7-Augered Piles) 1 LSUM \$63,700.00 (\$63,700.00 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Deep Foundations: Mobilization of Rig A Concrete: Pile Cape (7-ach 9).00 cy x 3.00 cy x 3.	D Concrete Pier 3,75' sq x 3.0' ht 13 CUYD \$850.00 (\$10.62	D	Concrete Column Ftg 6.0' sq x 2.5' dp	27	CUYD	\$385.00	(\$10,395)
D Steel	D Steel Heam Kicker Support Steel (Collar Ties) 7 TONS \$5,750.00 \$38,00	D	Concrete Pier 3.75' sq x 3.0' ht	13	CUYD	\$850.00	(\$10,625)
D Steel FBeam Kicker Support Steel (Collar Ties) 7 TONS \$5,750.00 (\$38,008	D Steel Heam Kicker Support Steel (Collar Ties) 7 TONS \$5,750.00 \$38,00	D	Steel I-Beam Super Structure 30" tall (3-sections)	78	TONS	\$5,500.00	
D Steel Beam Support Steel (Steel to Steel Connect) 10 TONS \$5,500.00 (\$57,338)	D Steel I-Beam Support Steel (Steel to Steel Connect) 10 TONS \$5,500.00 (\$57,31	D	Steel I-Beam Kicker Support Steel (Collar Ties)	7	TONS	\$5,750.00	(\$38,008)
D Steel Structural 12" Zee Girt Framing 1,597 LNFT \$11.50 (\$18,366)	D	D	Steel I-Beam Support Steel (Steel to Steel Connect)	10	TONS	\$5,500.00	
D	D Epicore ER6.5 Roof Deck Ceiling 3,053 SQFT \$37.50 \$114,48	D	Steel Structural 12" Zee Girt Framing	1,597	LNFT	\$11.50	
D 5/8" CDX Roof Sheathing 3,053 SQFT \$2.00 \$(\$6,106)	D 5/8" CDX Roof Sheathing 3,053 SQFT \$2.00 \$2.00 \$2.00	D	Epicore ER6.5 Roof Deck Ceiling	3,053	SQFT	\$37.50	
D	D	D	5/8" CDX Roof Sheathing	3,053	SQFT		
D	D	D	Peterson Alum Metal Roofing	3,053	SQFT	\$26.00	
D 90-lb Peel & Stick 3,053 SQFT \$1.00 \$3,053 D 60-mil TPO Fully Adheres Roofing System 857 SQFT \$18.00 \$15,426 D Floating Acoustical Clouds / Panels 1,760 SQFT \$18.00 \$31,680 D Wind Driven Rain Louver 331 SQFT \$245.00 \$81,095 D Stage Equip: Projection Screens 1 ALLW \$15,000.00 \$15,000 D Fire Sprinkler: Band Stand Area Only 4,643 SQFT \$2.50 \$11,608 D Electrical: Band Stand Area Only 4,643 SQFT \$5.50 \$25,537 D Deep Foundations: Piles 1 LSUM \$63,700.00 \$63,700.00 A Deep Foundations: Piles 1 LSUM \$63,700.00 \$12,600 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) 63 CUYD \$385.00 \$24,255 A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,000 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,840 A Design Completion Contingency (Hold Back Contingency) 1 ALLW 30,000.00 \$30,000 Do Not Use This Line Scalation 0,000% \$0 Status Rejected Sub Default Insurance 1,500% (\$10,463) Comments Design Completion Property 1,7500 \$22,250 IT, Scheduling & PROCOF 0,242% \$1,905 Insurance 1,175% \$39,757 P&P Bonds 0,732% \$65,086	D 90-lb Peel & Stick 3,053 SQFT \$1.00 (\$3,050 D G0-mil TPO Fully Adheres Roofing System 857 SQFT \$18.00 (\$15,42 D Floating Acoustical Clouds / Panels 1,760 SQFT \$18.00 (\$31,61 SQFT SQFT \$18.00 \$31,61 SQFT \$245,00 \$34,64 SQFT \$245,00 \$34,64 SQFT \$245,00 \$34,64 SQFT \$34,00 \$34,00 SQFT \$34,00 \$34,00 SQFT	D	Front Face Infill of Steel Beam: Alum Fascia	3,090	SQFT		
D 60-mil TPO Fully Adheres Roofing System 857 SQFT \$18.00 \$315,426	D 60-mil TPO Fully Adheres Roofing System 857 SQFT \$18.00 \$15,42	D	90-lb Peel & Stick	3,053		\$1.00	
D	D	D	60-mil TPO Fully Adheres Roofing System	857	SQFT	\$18.00	
D	D	D	Floating Acoustical Clouds / Panels	1,760	SQFT		
D Stage Equip: Projection Screens 1 ALLW \$15,000.00 \$15,000.00 D Fire Sprinkler: Band Stand Area Only 4,643 SQFT \$2.50 \$2.50 \$11,608 D Electrical: Band Stand Area Only 4,643 SQFT \$5.50 \$25,537 D Deep Foundations: Piles 1 LSUM \$63,700.00 \$63,700.00 A Deep Foundations: Polies 7-Augered Piles 315 LNFT \$40.00 \$12,600 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) 63 CUYD \$385.00 \$24,255 A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,000 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,840 A Design Completion Contingency (Hold Back Contingency) 1 ALLW 30,000.00 \$30,000 Do Not Use This Line	D Stage Equip: Projection Screens 1	D	Wind Driven Rain Louver	331	SQFT	\$245.00	
D Fire Sprinkler: Band Stand Area Only 4,643 SQFT \$2.50 \$11,608 D Electrical: Band Stand Area Only 4,643 SQFT \$5.50 \$(\$25,537) D Deep Foundations: Piles 1 LSUM \$63,700.00 \$(\$63,700) A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) 63 CUYD \$385.00 \$24,255 A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,000 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,840 A Add Services from Design team to redraw \$0 A Design Completion Contingency (Hold Back Contingency) 1 ALLW 30,000.00 \$30,000 Do Not Use This Line	D Fire Sprinkler: Band Stand Area Only 4,643 SQFT \$2.50 \$11,60	D	Stage Equip: Projection Screens	1	ALLW		
D Electrical: Band Stand Area Only	D Electrical: Band Stand Area Only	D	Fire Sprinkler: Band Stand Area Only	4,643			
D Deep Foundations: Piles 1 LSUM \$63,700.00 (\$63,700)	D Deep Foundations: Piles	D	Electrical: Band Stand Area Only	1	SQFT		
A Deep Foundations: Piles (7-Augered Piles) 315 LNFT \$40.00 \$12,600 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500 A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) 63 CUYD \$385.00 \$24,255 A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,000 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,840 Add Services from Design team to redraw \$0 A Design Completion Contingency (Hold Back Contingency) 1 ALLW 30,000.00 \$30,000 Do Not Use This Line \$\$ (\$697,546)\$ Comments \$\$ Usa Default Insurance 1.500% (\$10,463)\$ Comments \$\$ Design Contingency 7.000% (\$58,055)\$ MCF Contingency 7.000% (\$21,240)\$ IT, Scheduling & PROCOF 0.242% (\$1,905)\$ Insurance 1.175% (\$9,767) P&P Bonds 0.732% (\$6,086)	A Deep Foundations: Piles (7-Augered Piles) 315 LNFT \$40.00 \$12,60 A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,50 A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) 63 CUYD \$385.00 \$24,25 A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,00 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,84 Add Services from Design team to redraw \$9 A Design Completion Contingency (Hold Back Contingency) 1 ALLW 30,000.00 \$30,000 Do Not Use This Line \$9 Date Generated 13-Jul-20 Escalation 0.000% \$3 Status Rejected Sub Default Insurance 1.500% (\$10,46) Comments Design Contingency 7.000% (\$58,056) Fee 5.000% (\$42,056) IT, Scheduling & PROCOF 0.242% (\$1,900) Insurance 1.175% (\$9,760) Insurance 1.175% (\$9,760) Insurance 1.175% (\$9,760) P&P Bonds 0.732% (\$6,056) Design Contingency 1.175% (\$9,760) Insurance 1.175% (\$9,760) Insurance 1.175% (\$9,760) Insurance 1.175% (\$9,760) Its continue 1.175% (\$9,760) Its	D	Deep Foundations: Piles	1			
A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,500.00 A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) 63 CUYD \$385.00 \$24,255 A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,000 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,840 \$0 \$0 Add Services from Design team to redraw \$0 A Design Completion Contingency (Hold Back Contingency) 1 ALLW 30,000.00 \$30,000 \$0 Not Use This Line \$13-Jul-20 Escalation 0.000% \$0 Status Rejected Sub Default Insurance 1.500% (\$10,463) \$0 Design Contingency 7.000% (\$58,055) \$0 MCF Contingency 7.000% (\$21,240) \$1 Fee \$5.000% (\$42,051) \$1 Insurance 1.175% (\$9,767)	A Deep Foundations: Mobilization of Rig 1 LSUM \$7,500.00 \$7,50 A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) 63 CUYD \$385.00 \$24,25 A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,00 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,84 Add Services from Design team to redraw \$30,000.00 \$30,000 \$3	Α	Deep Foundations: Piles (7-Augered Piles)	315	LNFT		
A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) 63 CUYD \$385.00 \$24,255 A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,000 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,840 Add Services from Design team to redraw \$0 A Design Completion Contingency (Hold Back Contingency) 1 ALLW 30,000.00 \$30,000 Do Not Use This Line \$ (\$697,546) Date Generated 13-Jul-20 Escalation 0.000% \$0 Status Rejected Sub Default Insurance 1.500% (\$10,463) Comments Design Contingency 7.000% (\$21,240) Fee 5.000% (\$42,051) IT, Scheduling & PROCOF 0.242% (\$1,905) Insurance 1.175% (\$9,767) P&P Bonds 0.732% (\$6,086)	A Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp) A USA Shade & Fabric Structured Band Stand A Add for Back Side of the Stage for Articulation Add Services from Design team to redraw A Design Completion Contingency (Hold Back Contingency) Do Not Use This Line Date Generated 13-Jul-20 Rejected 13-Jul-20 Rejected 13-Jul-20 Status Rejected 13-Jul-20 Status Rejected 13-Jul-20 Sub Default Insurance Design Contingency MCF Contingency MCF Contingency Fee 17. Scheduling & PROCOF 11. ALLW 15.00% (\$10.46 17. Scheduling & PROCOF 17. Scheduling & PROCOF 18. P&P Bonds (\$6.97.54 18. POON (\$5.0.58 (\$6.97.54 18. Poon (\$6.97.54 18. Po	Α	Deep Foundations: Mobilization of Rig	1	LSUM		
A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,000 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,840 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0	A USA Shade & Fabric Structured Band Stand 1 ALLW \$270,000.00 \$270,000 A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,84 Add Services from Design team to redraw \$30,000.00 \$30,000 Do Not Use This Line \$\$\$ Date Generated 13-Jul-20 \$\$\$ Rejected \$\$\$ Rejected \$\$\$ Sub Default Insurance 1.500% \$10,460 Comments \$\$\$ MCF Contingency 7.000% \$58,050 MCF Contingency 3.000% \$21,240 Fee 5.000% \$21,240 IT, Scheduling & PROCOF 0.242% \$1,900 Insurance 1.175% \$1,900 Insur	Α	Concrete: Pile Caps (7-each 9.0' sq X 3.0' dp)	63	CUYD		
A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,840 Add Services from Design team to redraw \$0 A Design Completion Contingency (Hold Back Contingency) 1 ALLW 30,000.00 \$30,000 Do Not Use This Line \$ (\$697,546) Date Generated 13-Jul-20 Escalation 0.000% \$0 Status Rejected Sub Default Insurance 1.500% (\$10,463) Comments Design Contingency 7.000% (\$58,055) MCF Contingency 3.000% (\$21,240) Fee 5.000% (\$42,051) IT, Scheduling & PROCOF 0.242% (\$1,905) Insurance 1.175% (\$9,767) P&P Bonds 0.732% (\$6,086)	A Add for Back Side of the Stage for Articulation 1,530 SQFT \$28.00 \$42,84 Add Services from Design team to redraw 30,000.00 \$30,000 Do Not Use This Line (\$697,54) Date Generated 13-Jul-20 Escalation 0.000% Status Rejected Sub Default Insurance 1.500% (\$10,46) Comments Design Contingency 7.000% (\$58,05) MCF Contingency 7.000% (\$58,05) MCF Contingency 3.000% (\$21,24) Fee 5.000% (\$42,05) Insurance 1.175% (\$9,76) P&P Bonds 0.732% (\$6,08)	Α	USA Shade & Fabric Structured Band Stand	1	ALLW	\$270,000.00	
Add Services from Design team to redraw A Design Completion Contingency (Hold Back Contingency) Date Generated 13-Jul-20 Status Rejected Sub Default Insurance 1.500% (\$10,463) Comments Design Contingency 7.000% (\$58,055) MCF Contingency 3.000% (\$21,240) Fee 5.000% (\$42,051) IT, Scheduling & PROCOF 0.242% (\$1,905) Insurance 1.175% (\$9,767) P&P Bonds 0.732% (\$6,086)	Add Services from Design team to redraw A Design Completion Contingency (Hold Back Contingency) Do Not Use This Line Comments Date Generated 13-Jul-20		Add for Back Side of the Stage for Articulation	1,530	SQFT		
Add Services from Design team to redraw	Add Services from Design team to redraw Sandon Sand						
Continue	Do Not Use This Line		Add Services from Design team to redraw				
Comments Status Comments Escalation Contingency	Date Generated 13-Jul-20 Escalation 0.000% Status Rejected Sub Default Insurance 1.500% (\$10,46)		Design Completion Contingency (Hold Back Contingency)	1	ALLW	30,000.00	\$30,000
Date Generated 13-Jul-20 Escalation 0.000% \$0 Status Rejected Sub Default Insurance 1.500% (\$10,463) Comments Design Contingency 7.000% (\$58,055) MCF Contingency 3.000% (\$21,240) Fee 5.000% (\$42,051) IT, Scheduling & PROCOF 0.242% (\$1,905) Insurance 1.175% (\$9,767) P&P Bonds 0.732% (\$6,086)	Date Generated 13-Jul-20 Escalation 0.000% \$ Status Rejected Sub Default Insurance 1.500% (\$10,46 Comments Design Contingency 7.000% (\$58,05 MCF Contingency 3.000% (\$21,24 Fee 5.000% (\$42,05 IT, Scheduling & PROCOF 0.242% (\$1,90 Insurance 1.175% (\$9,76 P&P Bonds 0.732% (\$6,08	Do Not Use This Line					(\$CO7 EAC)
Status Rejected Sub Default Insurance 1.500% (\$10,463) Comments Design Contingency 7.000% (\$58,055) MCF Contingency 3.000% (\$21,240) Fee 5.000% (\$42,051) IT, Scheduling & PROCOF 0.242% (\$1,905) Insurance 1.175% (\$9,767) P&P Bonds 0.732% (\$6,086)	Status Rejected Sub Default Insurance 1.500% (\$10,46) Comments Design Contingency 7.000% (\$58,05) MCF Contingency 3.000% (\$21,24) Fee 5.000% (\$42,05) IT, Scheduling & PROCOF 0.242% (\$1,90) Insurance 1.175% (\$9,76) P&P Bonds 0.732% (\$6,08)	Date Generated	13-Jul-20	Escalation	Т	0 000%	
Design Contingency 7.000% (\$58,055) MCF Contingency 3.000% (\$21,240) Fee	Design Contingency 7.000% (\$58,050 MCF Contingency 3.000% (\$21,240 Fee	-			irance		
MCF Contingency 3.000% (\$21,240) Fee 5.000% (\$42,051) IT, Scheduling & PROCOR 0.242% (\$1,905) Insurance 1.175% (\$9,767) P&P Bonds 0.732% (\$6,086)	MCF Contingency 3.000% (\$21,24) Fee 5.000% (\$42,05) IT, Scheduling & PROCOF 0.242% (\$1,90) Insurance 1.175% (\$9,76) P&P Bonds 0.732% (\$6,08)	Comments					(\$58,055)
IT, Scheduling & PROCOR 0.242% (\$1,905) Insurance 1.175% (\$9,767) P&P Bonds 0.732% (\$6,086)	IT, Scheduling & PROCOF 0.242% (\$1,90 Insurance 1.175% (\$9,76 P&P Bonds 0.732% (\$6,08						(\$21,240)
Insurance	Insurance						(\$42,051)
P&P Bonds 0.732% (\$6,086)	P&P Bonds 0.732% (\$6,08				PROCOR		(\$1,905)
	(\$847,11			ILAL BOUNDS		0.732%	

MARCO ISLAND, FL Date: JULY 30, 2020

General Multi Bid Package - Value Management Detail

ITEM NO.

G2 Total Trellis Redesign for Savings





A = Add

ADD/DEDUCT	Description	Qty	Unit	Unit Cost	Cost
					\$0
D	Concrete Footings 1, 2, 3 & 4	52	CUYD	\$355.00	(\$18,567
D	Concrete Pedestal 1, 2, 3, & 4	9	CUYD	\$1,400.00	(\$12,684
D	CMU Columns @ Trellises	718	SQFT	\$28.00	(\$20,110
D	Stone Veneer	2,720	SQFT	\$48.00	(\$130,560
D	Granite Caps	40	EACH	\$185.00	(\$7,400
D	Aluminum Trellis	1	LSUM	\$368,250.00	(\$368,250)
D	Reduction in SQFT / Materials of Trellis System	810	SQFT	\$195.00	(\$157,950)
					\$0
					\$0
					\$0
					\$0
					\$0
	Add Services from Design team to redraw				\$0
	Design Completion Contingency				\$0
Do Not Use This Line					
					(\$157,950)
Date Generated	13-Jul-20	Escalation		0.000%	\$0
Status	Approved	Sub Default Insu		1.500%	(\$2,369)
Comments		Design Continge		7.000%	(\$13,146)
		MCF Contingend	су	3.000%	(\$4,810)
		Fee		5.000%	(\$9,522)
		IT, Scheduling &	PROCOF	0.242%	(\$431)
		Insurance		1.175%	(\$2,212)
		P&P Bonds		0.732%	(\$1,378)
					(\$191,818)



ASSUMPTIONS, CLARIFICATIONS AND ALLOWANCE LOG





 MARCO ISLAND VETERANS' PARK Marco Island, FL
 60% Construction Document Clarifications & Assumptions July 6, 2020

DOCUMENT ACKNOWLEDGEMENT

1. The 60-percent Construction Document estimate is based on Project Documents per Manhattan Documents Log attached.

GENERAL ITEMS

- This estimate includes a Construction Schedule that assumes an NTP and approved building permit
 no later than January 8, 2021 with a construction duration of 11 months to achieve Final Completion.
 This schedule assumes no interruption in flow of construction resulting from funding source delays or
 the effect of any COVID 19 implications on construction. If these matters affect the schedule, the
 Schedule and cost will require adjustment.
- 2. We have excluded any costs for hazardous materials removal or mitigation, or Tiff Fees for contaminated soils. These fees have and will continue to be paid directly by the Owner.
- 3. The Owner is assumed to provide an "all risk" (Builders Risk) policy with terms, limits, form and deductibles acceptable to the Contractor.
- 4. This estimate assumes an unencumbered use of the project site, including air-rights, in accordance with the Site Management Plan included herein. This site management plan does include a 8' high temporary construction fence and perimeter erosion control.
- 5. The following items are not included in this estimate, but should be taken into consideration or provided by the Owner or Design Team:
 - a) Design Fees for Architects and Consultants
 - Threshold inspection and inspection costs are by the Owner (materials testing is included as an allowance)
 - c) Cost of building permit and inspection fees are not included
 - d) The unloading, stocking, distribution, and installation of Owner FF&E items (e.g.: furniture, wall hangings, point of sale items, etc.)
 - e) We do not include any excavation, removal, undercutting, replacement, handling, or any other costs for any "unsuitable soils" for any reason. This includes rock, contaminated materials, hazardous materials, debris, groundwater, trash, waste, high moisture content, and/or anything other than "suitable soils" encountered below the existing top surface of the ground. Suitable soils





are defined as existing in a condition ready for immediate re-use as fill material and/or topsoil. All unsuitable soils shall be handled by change order per unit prices as encountered and all related delay will be added to the Contract Completion Date and the schedule on a day-for-day basis. This clarification supersedes any information contained in the Soils Report, etc. and shall supersede any differing or contradictory requirements anywhere else within the Bid and/or Contract Documents, such as "Un-Classified Soils" requirements, etc.

f) This estimate does not include the cost of any special inspections and Environmental Testing or permits. As example the Purchase of the Generator will require a permit with the Government agencies and the process is included in the scope. However the fee and completion of the form will be required to be performed by the University. Manhattan will provide the work associated with completing the process and Owner will need to sign forms and pay the nominal fee estimated as \$200.000, for Government Agencies having jurisdiction over the work.

SALES TAXES

The estimate includes sales tax. Florida State sales tax on materials and goods is included, in accordance with State Statutes. It is understood that the Owner will perform Sales Tax Savings and will institute a Direct Owner Purchase Plan to recover the Sales Tax Savings on only major material items and the deduct to the GMP will be only for the materials and sales tax with no GMP mark-up change.

BP02D SELECTIVE SITE DEMOLITION

 Site demolition is based off limited investigation of the project site and the Demolition Plan, Sheet D-01, of the construction plans. Any existing underground utilities requiring modification or relocation not shown on the provided construction documents are excluded.

BP03A CAST IN PLACE CONCRETE

- Foundations for Restrooms and Bandstand are included within the estimate. Due to lack of design noted sizes are detailed with the estimate.
- 2. We have included the structural fill required to raise the Band Stand slab 3.0' above finish grade.

BP05A STRUCTURAL STEEL - METAL JOIST - METAL DECK

- 1. No special coating / paint or sandblasting for Bandstand structural steel has been included.
- We have not included any galvanized structural steel for the Bandstand.

BP06A ROUGH CARPENTRY: WOOD TRUSSES / ROOF SHEATHING

1. Restroom trusses are included as wood with a 5/8" CDX roof sheathing based on a 5/12 pitch.





BP06D MILLWORK

 Restroom countertops are based on plastic laminated countertops; we have not included any type of stone countertops.

BP07A WATERPROOFING / JOINT SEALANTS

1. Standard waterproofing and joint sealant requirements are included.

BP07C METAL ROOF PANELS

- Metal roofing is included as Peterson Aluminum Tite-Loc Plus .032 aluminum panels with 16-inch wide, 2-inch high seams.
- Soffits and exterior ceilings at the restroom building are included as an aluminum system.

BP07E MEMBRANE ROOFING

 Bandstand roofing is based on a 60mm fully adhered TPO roofing system over tapered rigid insulation.

BP08B ENTRANCES / STOREFRONTS / GLASS & GLAZING

Windows are included as non-impact / non-operable aluminum framed windows.

BP09A STUCCO

- All stucco is included with a sand / float finish. All other finish textures are excluded.
- 2. All stucco is included with painted finish. Integral color is excluded.
- 3. Stucco ceiling are included as called for in the plans.

BP09B DRYWALL AND STUD FRAMING

Drywall and framing are included as standard interior construction with level 4 finish.

BP09C ACOUSTICAL / ACOUSTICAL CEILINGS

1. Acoustical panels at the band stand are included as floating "clouds" acoustical panels. We have not included any controls, winches etc. to control and / or adjust heights nor angles of the system.

BP09H PAINTING & COATINGS

Painting finish is included as typical requirements similar to Sherwin-Williams requirements.





- Interior floor at the bandstand and bathroom building is included as sealed concrete. Tile or other flooring materials are excluded.
- Wall finishes at the bandstand and bathrooms are painted finishes. No tile or other wall finishes are included.

BP10E SIGNAGE

1. We have included Life Safety / ADA signage as an allowance.

BP11E PROJECTION SCREENS

1. We have included within the Bandstand an allowance for projection screens.

BP21A FIRE SUPPRESSION

- Design & Install a new Wet Fire Sprinkler System in accordance with NFPA 13, NFPA 14, NFPA 20
 and local codes as per DD drawings dated 6/29/2018. Fire Suppression Contractor to begin work on a
 flange, located approximately one foot off finished floor. The occupancy of this facility is understood to
 be light hazard and ordinary hazard.
- 2. Wet System is designed using Schedule 40 CPVC Blazemaster piping and materials.
- 3. We do not include any fire suppression pump for the Restroom or the Bandstand.

BP22A PLUMBING

- 1. Estimate includes a complete Plumbing system that complies with all State, local and ADA codes.
- 2. Plumbing Fixtures are commercial American Standard (or Equal).
- 3. Domestic Water piping is CPVC with solvent weld joints.
- 4. Sanitary waste piping and storm piping is based on PVC.

BP23A HVAC

- 1. Estimate includes a complete Heating, Venting and Air Conditioning system that complies with all ASHRE, State, and local codes. Units will be Mini Split units and ceiling mounted exhaust fans.
- Ductwork (Air Distribution) shall be sheet metal and installed according to SMACNA standards.
- 3. No test and balance is included.
- Thermostats are included as low voltage type.





BP26A ELECTRICAL

- Estimate includes all conduit, wire, mc and junction boxes switchgear, disconnects, power connections and feeders for a complete Electrical system that complies with all, State, and local codes.
- Estimate includes a complete furnished and installed lighting system.
- 3. An allowance has been included to furnish and install a complete site lighting package, including hardscape, landscape lighting, ID / Decretive lighting.
- An allowance has been included to furnish and install a complete IT / Wi Fi system and CCTV.

BP31A EARTHWORK

- Silt fence was not shown on the 60% construction documents. Its installation is assumed to be a single layer silt fence (see Detail 2, Sheet C-02) located at the project limits as shown on Sheet C-01 Best Management Plan.
- Remediation of hazardous materials, contaminated soils, or other unsuitable soils is excluded.
- 3. On-site soil is assumed to be suitable for re-use as fill material and/or topsoil material.

BP31F SPECIAL FOUNDATIONS

- 1. We have included within the estimate augured cast piles for the support of the steel members for the Bandstand. Augered depths are included at 40.0' depth based on <= 16" diameter piles.
- 2. We have not included any pile load test; if required include an additional \$30,000 for a load test.

BP32A ASPHALT PAVEMENT / CURBS

- Asphalt pavement and base types are assumed to match Section A-A, Sheet C-09 of the 60% construction documents. This section indicates that 1" Type FC 9.5 Asphaltic Concrete, 1-1/2" Type SP 12.5 Asphaltic Concrete, 8" Limerock Base w/ Prime (LBR=100), and 12" Subgrade Stabilization are to be used in all standard use and heavy duty use pavement areas.
- Per Section A-A, Sheet C-09, 2' Valley Gutter is assumed to separate the parking stalls from the drive aisle along Lambert Drive. 2' Valley Gutter is assumed to separate the parking stalls from the drive aisle on Elkcam Circle West on the northeast side of the road where the proposed drainage system is being installed.
- 3. Curb adjacent to sidewalks and landscaped islands is assumed to be FDOT Type D curb.
- 4. Milling existing asphalt is assumed to be 2-1/2" in depth, based on the asphaltic concrete sectional depth of Section A-A, Sheet C-09.





BP32C UNIT PAVING

1. Crosswalks through parking areas or roadways are assumed be constructed from vehicular pavers in lieu of asphalt pavement.

BP32H PLANTING / SOD / TREES

1. Tree relocation process is included as removing tree from existing location and transplanting directly to proposal locations. Intermediate storage / holding of trees between removal and final transplant is excluded.



BP32I IRRIGATION

Irrigation currently has no design criteria; therefore we have included irrigation as an allowance.

BP32M BOARDWALKS

1. Boardwalk is included as an IPE deck system elevated no more than two feet higher than the existing seawall cap.

BP33A SITE UTILITIES

- 1. Unlabeled storm structures on Sheets C-04 and C-05 are included as yard drains.
- Unlabeled storm structures on Sheet C-07 are included as Type C Grate Inlets and the drainage culverts connecting them are included as 18" RCP.
- Potential removal / replacement of existing Elkcam Road West on Sheet C-07 for installation of storm utility drainage is excluded. The estimate includes the drainage system will be installed under the proposed parking stalls.
- 4. Assumed existing grate inlet at Structure 71 location on Sheet C-05 is to be removed / replaced by FDOT Type D modified inlet per the callout on the plan. Detail for Type D modified inlet is not shown on provided 60% documents.



► Allowances

Allowances listed below are inclusive of labor, materials, equipment, subcontractor overhead and subcontractor fee unless noted as "Material Allowances".

Allowances noted as material allowances are inclusive of material delivered jobsite including sales tax as applies to the project. Material allowances do not include waste, labor, subcontractor overhead or subcontractor fee.

Bid Package	Allowance Description	Cost
BP10E Signage	Allowance for Life Safety / ADA signage	\$30,000.00
BP11E Projection		
Screens	Allowance for Projection Screens	\$15,000.00
BP26A Electrical	Allowance for Site Lighting	\$125,000.00
BP26A Electrical	Allowance for IT / CCTV / WiFi	\$65,000.00
BP32I Irrigation	Allowance for Irrigation system	\$126,563.00



SITE MANAGEMENT PLAN



► SITE MANAGEMENT PLAN | CITY OF MARCO ISLAND VETERANS' COMMUNITY PARK









DOCUMENT LOG



MARCO ISLAND VETERANS PARK DESIGN DEVELOPMENT DOCUMENT LOG

Discipline	Drawing No.	<u>Drawing Title</u>	Revision	Drawing Date	Set Name
Architectural	CS	ARCHITECTURAL COVER SHEET	0	5/29/2020	Design Development Documents 04-03-20
Architectural	A1	RESTROOM PLAN	0	5/29/2020	Design Development Documents 04-03-20
Architectural	A2	BAND SHELL PLAN	0	5/29/2020	Design Development Documents 04-03-20
Architectural	A3	BAND SHELL ELEVATIONS	0	5/29/2020	Design Development Documents 04-03-20
Architectural	A4	BAND SHELL ELEVATIONS	0	5/29/2020	Design Development Documents 04-03-20
Architectural	A5	BAND SHELL SECTION	0	5/29/2020	Design Development Documents 04-03-20
Architectural	A6	BAND SHELL RCP	0	5/29/2020	Design Development Documents 04-03-20
Architectural	A7	3D VIEWS	0	5/29/2020	Design Development Documents 04-03-20
Civil	A-00	CIVIL COVER SHEET	0	5/29/2020	60% Construction Documents 04-03-20
Civil	A-01	GENERAL NOTES	0	5/29/2020	60% Construction Documents 04-03-20
Civil	A-02	EXISTING CONDITIONS	0	5/29/2020	60% Construction Documents 04-03-20
Civil	A-03	AERIAL SITE PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	D-01	DEMOLITION PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	D-02	TREE MITIGATION PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	D-03	TREE MITIGATION SPECIFICATIONS	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-01	BEST MANAGEMENT PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-02	BEST MANAGEMENT DETAILS	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-03	OVERALL SITE PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-04	PAVING GRADING & DRAINAGE	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-05	PAVING GRADING & DRAINAGE	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-06	PAVING GRADING & DRAINAGE	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-07	PAVING GRADING & DRAINAGE	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-08	PAVING GRADING & DRAINAGE DETAILS	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-09	CROSS SECTION MAP & CROSS SECTIONS	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-10	PAVEMENT MARKING & SIGNAGE	0	5/29/2020	60% Construction Documents 04-03-20
Civil	C-11	UTILITY PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	LI-01	LIGHTING PLAN- OVERALL	0	5/29/2020	60% Construction Documents 04-03-20
Civil	LI-02	LIGHTING DETAILS	0	5/29/2020	60% Construction Documents 04-03-20
Civil	LI-03	LIGHTING SPECIFICATIONS	0	5/29/2020	60% Construction Documents 04-03-20
Civil	H-01	HARDSCAPE PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	H-02	HARDSCAPE PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	H-03	HARDSCAPE PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	H-04	HARDSCAPE PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	H-05	HARDSCAPE PLAN	0	5/29/2020	60% Construction Documents 04-03-20
Civil	H-06	HARDSCAPE DÉTAILS	0	5/29/2020	60% Construction Documents 04-03-20
Civil	H-07	HARDSCAPE DETAILS	0	5/29/2020	60% Construction Documents 04-03-20

Discipline	Drawing No.	Drawing Title	Revision	Drawing Date	<u>Set Name</u>
Civil	H-08	HARDSCAPE DETAILS	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	H-09	SIGNAGE DETAILS	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	H-10	BOARDWALK DETAILS	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	H-11	SITE FURNISHINGS	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	H-12	SITE FURNISHINGS	0	5/29/20	20 60% Construction Documents 04-03-20
Cívil	L-01	LANDSCAPE PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	L-02	LANDSCAPE PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	L-03	LANDSCAPE PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	L-04	LANDSCAPE PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	L-05	LANDSCAPE PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	L-06	LANDSCAPE DETAILS	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	L-07	LANDSCAPE SPECIFICATIONS	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	I-01	IRRIGATION PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	I-02	IRRIGATION PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	I-03	IRRIGATION PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	1-04	IRRIGATION PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	I -0 5	IRRIGATION PLAN	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	1-06	IRRIGATION DETAILS	0	5/29/20	20 60% Construction Documents 04-03-20
Civil	I-07	IRRIGATION DETAILS & SPECIFICATIONS	0	5/29/20	20 60% Construction Documents 04-03-20